



Design Manual

October 2018 v1

Contents

WELCOME	3
OVERVIEW	4-5
PROCESS	6
HELPFUL HINTS	7
CONTRACTOR ACKNOWLEDGEMENT	8
CLUB LAYOUT	9
• Components	10-16
• Ceilings	17-18
NON-TRADITIONAL LEASE SPACES	19-22
CLUB LAYOUT SAMPLES	23-29
FINISHES & MATERIALS	30
• Paint, Flooring, Ceilings & Soffits, and Miscellaneous	31-37
COLOR SCHEMES	38-39
• Elements Scheme	40-46
• Gallery Scheme	47-53
INTERIOR FIXTURES & ACCESSORIES	54
• Lighting	55-56
• Member Lobby Furniture	57-59
• Guest Lobby Furniture	60
• Equipment	61
• Accessories	62-64
BUILDING SYSTEMS	65
• Mechanical/Electrical/Plumbing	66-69
• I.T. (Information Technology)	71-72
• Security	73-76
• Sound	76
SIGNAGE	77
• Exterior Signage	78-79
• Interior Signage & Graphics	79
APPENDIX	80-119
DESIGN MANUAL REVISION TRACKING	120

Welcome

Anytime Fitness is the world's largest co-ed fitness concept with more than 3 million members. To maintain brand consistency around the globe, Fabiano Designs International created an exclusive design language that gives our franchisees the opportunity to choose one of two color schemes to compliment their individual personality and desired club culture.

With that in-mind, it is vital that our franchisees adhere to every aspect of the Anytime Fitness design standards (specified in this manual) to ensure the brand remains strong and cohesive in every community and every nation.

This document, along with the prototype drawings, will provide information on design, construction, materials, finishes and details. Share this information with your architect, engineers and contractors to ensure your club is being built to Anytime Fitness standards. Your CDM (Construction Design Manager) and Franchise Business Consultant will be available to answer any questions that you may have, so don't hesitate to ask.

Thank you for choosing to be a part of the Anytime Fitness franchisee family! We look forward to helping you grow and prosper in the coming years!

Best regards,

The Anytime Fitness Corporate Team



"Welcome to the Anytime Fitness family! Use this document to help get your club up-and-running in the most effective manner. Remember, purple is a powerful color, so display it proudly, but properly!"

– *Captain Runningman*

Overview

One of the benefits of being an Anytime Fitness franchisee – compared to a solo venture – is the brand recognition that comes with being a part of our franchise family. As the franchisor, we are here to assist you and protect the brand you have purchased. We have prepared this book to guide you through the build-out process and maintain the integrity of our brand for the benefit of the entire franchise and member community.

BASE REQUIREMENTS

Once you have selected a site, you will need to ensure it meets the minimum requirements before proceeding with the design of your club and prior to signing your lease.

- The space must be able to achieve a minimum ceiling height of 10 feet throughout the entire space on all floors or levels.
- An open ceiling design is preferred.
- The space must be a minimum of 40 feet in width.

DESIGN

Your Construction Design Manager (CDM) will contact you to initiate the design process of your club. They will take you through the process step-by-step and will be your subject matter expert for all things design and construction related.

DESIGN APPROVAL

Your CDM will guide you through the design process to create your club layout. The approved design will be detailed in a document known as the “Compliance Drawing”, which will include your finish materials. The Compliance Drawing is the agreement on how your club will be constructed. Under no circumstance are you to deviate from the approved Compliance Drawing. If you feel a change is necessary, you must obtain written approval from your CDM in advance.

NATURAL RESOURCES

Your space may include an existing element that could add an interesting feature to your club. Anytime Fitness encourages you to explore the incorporation of such elements into the design of the space. A few examples include:

- A brick wall can be exposed to be a feature of the space.
- Wood or metal trusses or columns can be cleaned, stripped, or left exposed to showcase the building structure.

“Design is thinking...made visual...” - Saul Bass



Overview

ARCHITECTURAL SERVICES

You will need to engage the services of a registered architect to create the final set of construction documents for your club. Franchisees building their first club, are required to use the AF Designated Architect, Wilkus Architects. Their brand knowledge and industry experience makes them uniquely qualified for this task. If you are a multi-club franchisee and choose to use an architect other than the Designated Architect, you will be required to match all details and specifications accurately, to ensure Anytime Fitness brand standards are met.

Designated Vendor: Wilkus Architects – Brittany Bauer

Customer Service: 952-941-8660

bmb@wilkusarch.com

PROJECT MANAGEMENT SERVICES

Looking for help with your build-out? Cushman Wakefield is the preferred vendor, that can provide project management services to help you manage the overall build out process, including General Contractor bidding & selection, scheduling, GC management and oversight, weekly project calls, pay application reviews, and final close out. This program will allow you time to work on your marketing, presale, hiring and training.

Preferred Vendor: Cushman & Wakefield – Bruce Walwark

Customer Service: 952-820-8794

bruce.Walwark@cushwake.com

SITE SURVEY SERVICES


Part of the process to get your construction documents completed, is to provide an accurate set of as-built drawings of your leased space to the Architect. One option, is to have the Landlord provide a complete set of architectural, mechanical, electrical and plumbing plans, from their records. However, those plans may not be available from the Landlord, which can be fairly common, due to multiple changes in ownership. The other option, will require you to have the space surveyed by a qualified site survey company or a qualified architect.

Recommended Vendor: National As Built Inc. – Madjid Hoseiny

Customer Service: 972-342-7070

info@nationalasbuilt.com

***“You have to go whole heartedly into anything in order to achieve anything worth having”
– Frank Lloyd Wright***



Process

The build-out of your club is important for brand consistency and ensures the basic functionality of your facility for members and staff. Avoid costly delays by following these important steps.

1. Work with your Franchise Business Consultant and/or Operations Opening Coordinator on the Site Approval for your club.
2. Your Construction Design Manager (CDM) will contact you to initiate the design of your club. You will work with your CDM to create the approved compliance drawing for your club. You will need to provide 3 main pieces of information:
 - Site Conditions: This is accomplished through as-built plans or a site survey.
 - Design Elements: Which of the optional elements you want in your club.
 - Color Scheme: Specify which of the available color schemes you would like for your club décor.
3. Contact one of the Designated Sign Vendors listed on the Vendor Portal (we recommend you get quotes from all three sign vendors) to initiate the process for approval, fabrication and installation of your exterior sign. This is a lengthy process, so don't delay.
4. Contract with the Designated Architect to create a full set of construction documents matching the detail and format of the Anytime Fitness prototype drawings. The Designated Architect has the experience and brand knowledge to meet this requirement.
5. Submit your construction documents for permits and approvals. It is recommended you contract with your architect to handle this step.
6. Submit your construction documents and schedule of values (SOV) forms to a minimum of three general contractors to obtain competitive bids. Allow 3 weeks for the bidding process. Once you receive your bids, you will need to qualify the numbers, select a general contractor, award the project, set a schedule with your GC and execute a contract.
7. You are required to submit a signed copy of the "Contractor Acknowledgment Form" (following pages) along with your detailed line item cost breakdown "Schedule of Values" (SOV) from the GC you have selected to your CDM.
8. Accept the premise from your landlord, this is your opportunity to make sure they have completed all work identified in the lease, if they have not, the Landlord needs to complete prior to you accepting the space.
9. Once you have received your permits and approvals, you are ready to begin construction. Make sure you have satisfied all of your lease obligations related to construction: i.e. certificate of insurance, approval of construction documents, contractor approval, etc.

Throughout this process, you will work with your Franchise Business Consultant on a series of tasks; ordering equipment, pre-sale, billing etc. They will walk you through these items.

NOTE: Anytime Fitness will create the original compliance drawing for new clubs at no cost to the franchisee. If an alternate plan or revisions are required, the franchisee will be responsible for any related costs to the Designated Architect.

Helpful Hints

CONSTRUCTION SCHEDULE

Review your construction timeline with your CDM, including plans for opening and before construction begins. Some materials like flooring and wall covering require a few weeks lead-time, so we recommend that you order your materials promptly, factor-in the estimated delivery dates and adjust your timeline as needed.

EXTERIOR SIGNAGE

Exterior signage can take 8-10 weeks from the time you start, to when the sign is installed on the building. You will want to get your sign installed as soon as possible to take advantage of the extra visibility for your presale.

OPENING DATES

Do **NOT** promise your members an opening date. Many times, a club's construction is delayed due to weather, city permits, contractors or deliveries. Instead, inform members that you are working toward a certain date range and their dues will not start until the club is officially open.

EQUIPMENT ORDERING

Remember you need to order your equipment at least 8-10 weeks before the desired delivery date. It is advisable to work with your Franchise Business Consultant and Equipment Representative at the beginning of the design process. The final equipment list and layout should be determined with your Equipment Representative and Franchise Business Consultant very early on. Once finalized, the equipment information and location must also be provided to your electrical contractor for coordination.

VERIFY MEASUREMENTS IN FIELD

If your landlord or real estate agent provides you with a plan of your space, you **MUST** double check all dimensions and conditions. The slightest inaccuracy can cause shortages of materials, additional costs, and potential construction delays. It is strongly recommended that you have a detailed site survey completed to accurately document the existing site conditions of your space. This can be completed by an architect or an experienced survey company (See page 5). Your CDM can help you determine what you have and need.



Contractor Acknowledgement

The intent of this document is to ensure that contractors and parties providing construction services in the construction of Anytime Fitness clubs have received a copy of the design manual required by Anytime Fitness, LLC, and that Anytime Fitness franchisees acknowledge that the construction of their clubs are subject to mandatory specifications. This document is not meant to replace a written agreement between the Anytime Fitness franchisee and its contractor or any party providing construction, or any applicable federal, state or local laws or regulations which may apply. Anytime Fitness, LLC makes no representation to either party as to the enforceability of any provision set forth herein on behalf of such party, and each signatory should review all agreements with their own professional advisors.

CONTRACTOR ACKNOWLEDGEMENT

The undersigned ("Contractor") certifies that it/he/she is being retained to provide construction services and/or project management for an Anytime Fitness fitness center to be located at:

Address _____

Contractor acknowledges that the Anytime Fitness Center is subject to a Franchise Agreement with Anytime Fitness, LLC ("Franchisor").

This acknowledgment certifies contractor receipt and review of the Franchisor's Design Manual, dated _____ (see cover of Design Manual), containing the required specifications of Franchisor with respect to the Anytime Fitness club, and fully understands the requirements set forth therein, including without limitation, with respect to materials required to be used. Contractor acknowledges and agrees that any variance from the Design Manual shall require Franchisor's prior written approval, and that material substitutions are not allowed. Any variance from the specifications set forth in the Design Manual not approved by Franchisor in writing must be remedied at Contractor's expense. By signing this acknowledgment, the undersigned represents that he or she is duly authorized and has legal capacity to execute and deliver this acknowledgment on behalf of contractor.

Contractor Name _____

Signature _____

Print Name _____

Title _____

Date _____

**FRANCHISEE TO SUBMIT THIS COMPLETED FORM AND THEIR SCHEDULE OF VALUES (SOV)
TO THEIR CDM, PRIOR TO OPENING.**



CLUB LAYOUT

Club Layout


Anytime Fitness clubs utilize a two door system, one for guest entry and one for member entry. A set of double doors are recommended. The location of these doors have a major impact on the flow and functionality of your club. Your doors will dictate the location of your guest and member lobbies, which, in-turn will determine the location of your main office. Once the location of your doors has been established, your CDM will use the following information to create the layout.

The configuration of your club may vary greatly from what is shown. This sample plan and the corresponding description of each item on the pages that follow will help you understand the various factors managed by your CDM in creating the most effective layout.

AREA/ FEATURE/ ELEMENT

- A – Member Lobby (Required)
- B – Guest Lobby (Required)
- C – Main Office (Required)
- D – Trainer's Office (Optional)
- E – Cardio Area (Required)
- F – Strength Training (Required)
- G – Functional Area (Required)
- H – Toilet/ Shower & Utility Block (Required)
- I – Free Weight Area (Required)
- J – Inspiration Wall (Required)
- K – Retail/Logo Wall (Required)
- L – Manifesto Wall (Required)
- M – Multi-Purpose Room (Optional)
- Not Shown – Tanning/Massage (Optional)

Your club must be able to accommodate the minimum equipment package for Cardio, Strength & Free Weights before optional elements can be included in the design. Your Franchise Business Consultant can provide direction of equipment options for your club.



See the following pages for description of the club layout.

	SPACE/ AREA	DESCRIPTION
A	Member Lobby 	USE: Short-term storage for member shoes, coats, and bags. SIZE: 10'-0" x 10'-0" min. LOCATION: Near front entry and Main Office to create engagement opportunity upon Member's entry into the club. CEILING: Open to the deck or 2' x 2' acoustic ceiling height 10'-0" to 12'-0" AFF. • SEE "CEILINGS & SOFFITS" FOR MORE INFORMATION. • SEE "INTERIOR FIXTURES & ACCESSORIES" FOR REQUIRED & RECOMMENDED FURNITURE, EQUIPMENT, AND ACCESSORIES. • SEE "BUILDING SYSTEMS" FOR MEMBER ENTRANCE SECURITY & MONITORING REQUIREMENTS.
B	Guest Lobby	USE: Guest waiting area and sign-in during sales hours. SIZE: 10'-0" x 17'-6" min. with minimum 7' wide opening view to main portion of the club. LOCATION: Accessed from double entry door. FEATURES: Retail Logo Wall and Inspiration Wall. CEILING: 2' x 2' acoustic ceiling recommended, height must be 10'-0" to 12'-0" AFF. • SEE "CEILINGS & SOFFITS" FOR MORE INFORMATION. • SEE "INTERIOR FIXTURES & ACCESSORIES" FOR REQUIRED & RECOMMENDED FURNITURE, EQUIPMENT, AND ACCESSORIES.
C	Main Office	USE: Manager & sales staff use during staffed hours. SIZE: Approximately 10'-0" x 10'-0" min. Walls to extend to the roof deck or 12'-0" minimum. LOCATION: Must be adjacent to the guest entrance lobby with direct sight lines to it. CEILING: 2' x 2' acoustic ceiling is recommended, height 10'-0" A.F.F. COMPONENTS: Windows to provide visibility to the lobby and/or main club. Door should be equipped with lockable latch set and open into the main lobby. The office will house your security system, computer, audio system, business phone, and fax. • SEE "BUILDING SYSTEMS" FOR DATA, POWER, ACCESS, AND SECURITY & SURVEILLANCE EQUIPMENT REQUIRED.

	SPACE/ AREA	DESCRIPTION
D	Trainer's Office (optional)	USE: Trainer and staff use during staffed hours. SIZE: Approximately 8'-0" x 10'-0". Walls to extend to the roof deck or 12'-0" minimum. Location: Location may vary, but it's most-often adjacent to the main office. CEILING: 2' x 2' acoustical is recommended, height 10'-0" A.F.F. COMPONENTS: Door to be equipped with lockable latch set. • SEE "INTERIOR FIXTURES & ACCESSORIES" FOR LIGHTING REQUIREMENTS. • SEE "BUILDING SYSTEMS" FOR HVAC. • SEE "BUILDING SYSTEMS" FOR DATA AND POWER REQUIREMENTS.
E	Cardio Area	LOCATION: Adjacent to windows with view to the exterior (preferred); may be adjacent to strength training. CEILING: No ceiling – an open deck design is recommended. With an open ceiling, the use of dryfall white paint is required. • SEE "BUILDING SYSTEMS" FOR DATA, POWER, AND. HVAC REQUIREMENTS.
F	Strength Training	LOCATION: Centralized within club and adjacent to cardio area. CEILING: No ceiling – an open deck design is recommended using dryfall white paint. (Required) • SEE "BUILDING SYSTEMS" FOR DATA, POWER, AND. HVAC REQUIREMENTS.
G	Functional Training	USE: Group training and individual activities and exercises that are frequently performed with equipment such as kettlebells, battle ropes, medicine balls, etc. Size: 600 S.F – 1,000 S.F. LOCATION: Preferably adjacent to the Free Weights and against two walls in an open corner. The space must be adjacent to a minimum of one wall and cannot be free floating in the middle of the club. The area must be accessible from the main part of the club. It should not be enclosed in a room. Wood wall protection is recommended, refer to appendix for details. SIZE REQUIREMENT: An overall club area of 4,200 sq.ft. is typically required to accommodate a functional training area. If a functional training area and multi-purpose room will be included within the club, the size requirement will increase by the size of the second room/space.
	<u>Wall Protection is Recommended</u>	

	SPACE/AREA	DESCRIPTION
H	Toilet/Shower Room(s)	LOCATION: At the rear of your club. REQUIREMENTS: Toilet rooms and drinking fountains must be provided per plumbing code and ADA requirements. Clubs are required to provide single occupancy rooms as-follows: • (2) Toilet rooms with showers. • (1) Toilet room without a shower. • Additional toilets may be required by local codes. Have your architect of record verify the specific requirements for your club. • Doors for toilet and toilet/shower rooms must be screened from the main club. • Walls to extend to underside of roof deck or a 12'-0" min. • These are designed for single-use only and must not be set up for shared use in any way. Locker room-style bathrooms or multiple toilet bathrooms are <u>NOT</u> allowed. SIZE (TOILET/SHOWER ROOM): Sized to fit all necessary components below; greater than or equal to the minimum required by local codes or ADA requirements. COMPONENTS: Toilet Room: One toilet, one sink, mirror, and door closure with lockable latch set from the interior of the room. Toilet/Shower Room: One toilet, one sink, one shower, mirror, and door closure that is locked from the interior of the room. MATERIALS: Porcelain tile (as described in Section 2 finishes & materials) is required for all toilet and toilet/shower room floors and walls. Fiberglass enclosures can be used in the shower, however, tile is recommended. Porcelain tile shower floor or shower pan must be slip resistant and sloped to the shower drain. Tempered glass shower door or a rod hung, high-quality shower curtain with a heavy vinyl liner, are both acceptable. CEILING: Ceilings are required in all toilet & toilet/showers. If the walls for each room extend to the deck a vinyl wrapped acoustical ceiling system can be used. If the wall stops short of the deck, a hard lid, gypsum board ceiling is required. Ceiling height is 9'-0" A.F.F.. • SEE "APPENDIX" FOR CONSTRUCTION DETAILS & PHOTOS. • SEE "SIGNAGE" FOR INTERIOR SIGNAGE REQUIREMENTS. • SEE "INTERIOR FIXTURES & ACCESSORIES" FOR LIGHTING • SEE "BUILDING SYSTEMS" FOR POWER REQUIREMENTS. • SEE "CEILINGS & SOFFITS" FOR MORE INFORMATION.

	SPACE/AREA	DESCRIPTION
H	Utility Room	LOCATION: At the rear of your club. SIZE (UTILITY ROOM): Sized to fit and access all necessary components, including – but not limited to – water heater, mop sink, electrical panel, etc. Connected to restrooms via tile walkway. Walls should extend to underside of roof deck. COMPONENTS: Utility Room: One water heater, one mop sink, accessed by door locked from the exterior. CEILING: Recommend a 2' x 2' acoustical ceiling in utility rooms, open ceilings are allowed with walls built to the deck. • SEE "APPENDIX" FOR CONSTRUCTION DETAILS AND PHOTOS. • SEE "SIGNAGE" FOR INTERIOR SIGNAGE REQUIREMENTS. • SEE "INTERIOR FIXTURES & ACCESSORIES" FOR LIGHTING REQUIREMENTS. • SEE "BUILDING SYSTEMS" FOR POWER REQUIREMENTS. • SEE "CEILINGS & SOFFITS" FOR MORE INFORMATION.
	Tanning and/or Enclosed Aqua Massage Room(s) (Optional) Hydro Massage Lounge Room	USE: Accessible tanning or massage for members. LOCATION: Often adjacent to toilet/shower & utility room block. SIZE: 9'-0" W x 8'-6" D is the minimum size required, which is large enough to accommodate the tanning equipment and proper access to the bed. We recommend that your walls extend to the underside of the roof deck or a minimum of 12'-0". COMPONENTS: Door to be equipped with push button lock inside & keyed lock outside. CEILING: Ceilings are required. If the walls for each room extend to the deck a vinyl wrapped acoustical ceiling system can be used. If the walls stop short of the deck, a hard lid, gypsum board ceiling is required. Ceiling height is 10'-0" A.F.F.. LOCATION: Non-exercise area that opens to a portion of the club other than a restroom corridor and not into an area of activity; i.e. Free Weights, Functional Training, etc. Hydro Massage Room opening into a restroom corridor are required to be enclosed. SIZE: Area to be approximately 9'x9' with screen walls to provide semi private experience. Walls should be positioned so the member's head is not visible when the bed is in use. Doors are not utilized in this configuration. CEILING: Can be open, acoustical or gyp. board. • SEE "CEILINGS & SOFFITS" FOR MORE INFORMATION. • SEE "INTERIOR FIXTURES & ACCESSORIES" FOR REQUIRED & RECOMMENDED FURNITURE, EQUIPMENT, AND ACCESSORIES. • SEE "BUILDING SYSTEMS" FOR POWER, ACCESS, SECURITY & MONITORING REQUIREMENTS.

	SPACE/AREA	DESCRIPTION
I	Free Weight Area	LOCATION: View of the space slightly obstructed from main entry points. SIZE: 850 sq.ft. minimum to accommodate standard free weight equipment package. CEILING: No ceiling – an open deck design is recommended using specified dryfall white paint (required). Gypsum board soffit incorporated as a visual transition from adjacent space(s) is optional. Height of soffit to be 10'-0" to bottom of soffit, but it must coordinate with lobby ceiling height. • SEE "BUILDING SYSTEMS" FOR POWER & DATA REQUIREMENTS.
J	 Inspiration Wall	PURPOSE: For Members' use in defining goals and/or noting achievement, sales tool to communicate club culture to prospective members. LOCATION: Adjacent to guest lobby; a sidewall/separator between guest lobby and an adjacent space. SIZE: Wall to be 8'-0" H and 8'-0" W (or as defined in the Compliance Drawing). This will be a free-standing and self-supporting wall, therefore 6" metal studs with in-wall structural support are required – <u>bracing to ceiling/roof deck is NOT allowed</u>. COMPONENTS: "Inspiration" portion faces guest lobby. See the "Finish Schedule" for color-code information that applies to your design scheme. • SEE "APPENDIX" FOR CONSTRUCTION DETAILS AND PHOTOS.
K	 Retail Logo Wall	PURPOSE: Provides a welcoming first impression for guest and a merchandising opportunity. LOCATION: Must be immediately visible upon entrance to the guest lobby. This wall defines the parameters of the guest lobby. SIZE: Wall should be between 8' to 10' W (as defined in the Compliance Drawing). If there is no ceiling in the lobby, the wall should be 10' H. If there is a ceiling in the lobby, the framing must extend to the roof deck. The finish on the lobby side and the end of the wall should terminate at the lobby ceiling and it must wrap edge of the wall. MERCHANDISING INSERT: Prefabricated unit must be purchased through preferred vendor – refer to vendor portal for ordering. Glass shelves and mirror to be supplied by Owner or GC locally. • SEE "APPENDIX" FOR CONSTRUCTION DETAILS AND PHOTOS. • SIGNAGE: The "stacked" Anytime Fitness logo must be purchased through the Mandatory Vendor through the vendor portal. • Refer to "Interior Signage & Graphics Style Guide" for details on the graphic portion of the wall.

	SPACE/AREA	DESCRIPTION
L	Manifesto Wall 	PURPOSE: Create Visual Interest and enhance the brand personality LOCATION: In the back of the club with visibility to the main areas of the club. SIZE: Finished at 7' W x 10" H – NO Deviations of size allowed. Maintain 7' clear space in front of Manifesto Wall COMPONENTS: Graphic must face the workout area and be unobstructed by equipment. • SEE "APPENDIX" FOR CONSTRUCTION DETAILS AND PHOTOS • Refer to "Interior Signage & Graphics Style Guide" for details on the graphic portion of the wall.
M	Multi-Purpose Room (Optional)	USE: Instructor-led classes, Fitness on Request, personal training, and stretching. SIZE: This is determined by the size of your club. The overall club size must be a minimum of 5,000 sq.ft. to support a multi-purpose room. The minimum size for a multi-purpose room is 400 sq. ft. with a min. length and width of 20'. Clubs larger than 5,000 sq. ft. may be able to increase the size of a multi-purpose room up to 800 sq.ft club. LOCATION: Varies. CEILING: Walls should extend to the roof deck (recommended) or bottom of joist with 2' x 2' acoustic ceiling at 12'-14' for sound control. COLORS: Refer to "color schemes" section of this manual for required paint colors. SOFFIT: Prefabricated soffit is required. Refer to the Interior Signage & Graphic Style Guide. WINDOWS: Full height glass windows are not allowed for privacy reasons. Doors are to be clear sealed maple wood doors with a full glass window. • SEE "FINISHES & MATERIALS" FOR COLOR SCHEME REQUIREMENTS. • SEE "BUILDING SYSTEMS" FOR DATA, POWER, AND. HVAC REQUIREMENTS. • Refer to "Interior Signage & Graphics Style Guide" for details on the graphic portion of the wall.

Ceilings & Soffits

There are a variety of acceptable ceiling & soffit design options. Existing conditions, functionality, cost and personal preference are all factors for consideration.

MAIN CLUB AREA

An open ceiling design creates a more open inspirational environment and is strongly recommended. This design requires that all exposed elements (structural members, decking, pipes, spiral ductwork, conduit, etc.) be painted white as defined in this manual. Care must be taken to conceal wires and cabling if they are not installed in conduit. The open ceiling design can be enhanced by providing partial ceilings and soffits in select areas. Refer to the sections below for more detail.

If an acoustical ceiling is utilized in the main area of the club, it should be installed as high as possible to create an open feel.



The minimum allowable ceiling height for the main club area is 10'-0".

Under no circumstance will any ceiling height of less than 10'-0" be permitted.

PARTIAL ACOUSTIC CEILING(optional)

DESCRIPTION:

2' x 2' white acoustical ceiling systems with premanufactured edge trim installed in select areas. This will help with reducing the volume/space of select areas that benefit from a lower ceiling; Guest Lobby, Member Lobby & Hallways. The height of the ceiling is typically 10'-0" but may need to be raised to accommodate window heights. Exact specification for the ceiling and edge trim can be found in the "Finishes & Materials" section.

LOCATION: Member Lobby, Guest Lobby and Hallways.

GYPSUM BOARD SOFFIT (optional)

DESCRIPTION:

A gypsum board soffit, 36" W x 18" H, suspended using unistrut and all thread to create a "free-floating" look. The bottom of the soffit should be installed at the same height as adjacent suspended ceilings and/or the guest lobby. The ends of the soffit need to terminate at walls.

LOCATION:

Transition between the free weight area and the remainder of the club.

MULTI-PURPOSE ROOM


Acoustical ceilings are strongly recommended to reduce echoing and manage sound. The ceiling should be installed as high as possible with a minimum 10'-0". If an open deck design is utilized, it is strongly recommended that sound absorption/deadening be added to the ceiling.

TOILET AND SHOWER ROOMS

Ceilings are required. If the walls for each room extend to the deck, a vinyl wrapped acoustical ceiling system can be used. If the walls stop short of the roof deck, a hard lid gypsum ceiling is required.

"Open spaces embody the scientific knowledge that higher ceilings are better for health, improve brain connectivity, and feel more beautiful all around."

Sydney Franklin – Architizer.com





NON-TRADITIONAL
LEASE SPACES

Non-Traditional Lease Spaces

The most common/traditional type of shell construction is a single building with a concrete floor slab on grade. Additional consideration needs to be given to Non-Traditional Lease spaces that vary in type of construction, including but not limited to.

Categories:

- A. Spaces with Basements
- B. Spaces on a 2nd floor
- C. Spaces located in a structure with multiple floors
- D. Spaces with sound sensitive co-tenants; e.g. residential

The sections below will provide requirements and/ or areas of concern.

- Floor Systems
- Saw Cutting & Core Drilling
- Equipment
- Tile Membrane
- Floor Underlayment

FLOOR SYSTEMS

Spaces in categories “A”-“C” need to address the structural capabilities of the floor system. Based on an “Assembly Use” the floor system should have a minimum design live load of 125 pounds per square foot with additional consideration load from weights and equipment. It is recommended that a Structural Engineer is engaged to evaluate each floor system.

SAW CUTTING & CORE DRILLING

Additional precautions should to be taken when modifying the floor system for spaces located in categories “A” – “C”. Floor systems that are not located directly on the ground are typically designed with additional structural supports/reinforcing within the floor that are undetectable to the naked eye. If the structure/reinforcing is cut or altered, it can void the structural integrity of the entire building. Additional measures such as X-raying the floor may be necessary. Ensure the design professional and contractors involved with your club have done the necessary due diligence and taken the appropriate measures.

EQUIPMENT

Noise reduction platforms should be used in the Free Weight Area in spaces that fall into categories “A”-“D” to reduce noise for actives such as dead lifts. Refer to the portal for APPROVED/AUTHORIZED options.

TILE MEMBRANE

A membrane is required under the floor tile in the restroom/shower rooms of the club, for any space in category “A” or “B”. The membrane helps prevent leaking. There are many products on the market to choose from, including trowel on and membrane products. Some products require a specific floor drain to ensure a water tight seal. Here are a few recommended products.

- **Strataflex Waterproofing Membrane**

- Strataflex is a high strength, self-bonding, elastomeric sheet applied membrane and is designed for use under floor surfaces that require protection from water penetration.

- **REDGARD Waterproofing Membrane**

- An elastomeric waterproofing membrane for both commercial tile and stone application. Can be used as a slab-on-grade moisture vapor barrier under all types of floor coverings.

FLOOR UNDERLAYMENT

Flooring underlayment is required to reduce noise and sound transfer in categories “A”-“D”. Additional measures may be required depending on your situation

NOISE REDUCTION UNDERLAYMENT – To be used under Patcraft Luxury Vinyl Plank

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
NRU-1	Patcraft	S122V Groundworks	3' x 33'-4"	
Designated Vendor: Shaw Integrated Solutions (S.I.S.) Customer Service: 800-338-9479 anytime.fitness@shawinc.com				

NOISE REDUCTION UNDERLAYMENT – To be used under Patcraft Luxury Vinyl Plank

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
NRU-2	Patcraft	S109V Hush II	42" X 80'	
Designated Vendor: Shaw Integrated Solutions (S.I.S.) Customer Service: 800-338-9479 anytime.fitness@shawinc.com				

FLOOR UNDERLAYMENT (Continued)

SOUND REDUCTION MAT – To be used under Ecore Rubber in Free Weight Area

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
SRM-1	Ecore	4735 – 12mm	Rubber	
<u>Designated Vendor:</u> Ecore International, Inc. Customer Service: 515-450-2144 matt.koch@ecoreintl.com				

WHEELED TRAFFIC TRANSITION – Use where Ecore 4735 meets concrete

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
WTT-1	Johnsonite	CT-40-PL Black	½" Material to subfloor,	
Designated Vendor: Ecore International, Inc. Customer Service: 515-450-2144 matt.koch@ecoreintl.com				

RUBBER RAMP UP – To be used under flooring materials to create a flush transition

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
RP-1 RP-2	Johnsonite Johnsonite	LS-40 (use w/Carpet) LS-40-F (use w/ Turf)	Reduces ¼" to 0" Reduces 1/8" to 0"	
Designated Vendor: Shaw Integrated Solutions (S.I.S.) Customer Service: 800-338-9479 anytime.fitness@shawinc.com				

VINYL FLOORING TRANSITION STRIP – To be used between all flooring material changes

VINYL FLOORING TRANSITION STRIP TO BE USED FOR ALL FLOORING MATERIAL CHANGES				
	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
TS-1	Johnsonite	CE-40-C Black	12' "T" Molding Transition 12' Flex Track – MTC-00-A	
Designated Vendor: Shaw Integrated Solutions (S.I.S.) Customer Service: 800-338-9479 anytime.fitness@shawinc.com				



CLUB LAYOUT
SAMPLES

SAMPLE LAYOUT – 5,000 S.F. W/ MULTI-PURPOSE ROOM



Design Elements

- Retail/ Logo Wall
- Inspiration Wall
- Manifesto Wall

REQUIRED AMENITIES

- Member Lobby
- Guest Lobby
- Manager's Office
- Cardio Area
- Strength Training Area
- Free Weight Area
- Utility/ Storage Room (1)
- Restroom(s) without Shower (1)
- Restrooms with Shower (2)
- Functional Area

OPTIONAL AMENITIES

- Trainer's Office
- Multi-Purpose Room
- Tanning/ Massage Room


DESIGN HIGHLIGHTS

- Windows provide abundant natural light
- Shared double door entry promotes member engagement and accommodates equipment deliveries
- Guest Lobby
 - Defined by Manager's Office, Retail Logo Wall and Inspiration Wall
 - Clear line of site from Manager's Office
 - Member Lobby is screened from view
 - Free Weight Area is partially screened from view
- Retail Logo Wall immediately in front of guest door
- Cardio Area is immediately adjacent to front windows
- Multi-Purpose Room entrance is centrally located and visible from the guest lobby.
- Free Weight Area is screened without being closed off
- Shared corridor for Restrooms and emergency exit
- Functional Area is anchored by a wall with high visibility to the main area of the club

RECOMMENDED CONFIGURATION AND REQUIRED ELEMENTS


SAMPLE LAYOUT – 5,000 S.F. W/ MULTI-PURPOSE ROOM

RECOMMENDED EQUIPMENT



This plan provides a 600 S.F. dedicated functional training area in addition to a Multi-Purpose Room. The layout supports the minimal equipment package with space for optional pieces.

SAMPLE LAYOUT – 5,000 S.F. W/ NO MULTI-PURPOSE ROOM



Design Elements

- Retail/ Logo Wall
- Inspiration Wall
- Manifesto Wall

REQUIRED AMENITIES

- Member Lobby
- Guest Lobby
- Manager's Office
- Cardio Area
- Strength Training Area
- Free Weight Area
- Utility/ Storage Room (1)
- Restroom(s) without Shower (1)
- Restrooms with Shower (2)
- Functional Area

OPTIONAL AMENITIES

- Trainer's Office
- Tanning/ Massage Room


DESIGN HIGHLIGHTS

- Windows provide abundant natural light
- Shared double door entry promotes member engagement and accommodates equipment deliveries
- Guest Lobby
 - Defined by Manager's Office, Retail Logo Wall and Inspiration Wall
 - Clear line of site from Manager's Office
 - Member Lobby is screened from view
 - Free Weight Area is partially screened from view
- Retail Logo Wall immediately in front of guest door
- Cardio Area is immediately adjacent to front windows
- Free Weight Area is screened without being closed off
- Shared corridor for Restrooms and emergency exit
- Functional Area is anchored by a wall with high visibility to the main area of the club

RECOMMENDED CONFIGURATION AND REQUIRED ELEMENTS

SAMPLE LAYOUT – 5,000 S.F. W/ NO MULTI-PURPOSE ROOM

RECOMMENDED EQUIPMENT



This plan provides a 1,000 S.F. dedicated functional training area. The Torque rack system is positioned so it can be used from both the Free Weight Area and Functional Area. The layout supports the minimal equipment package with space for optional pieces.

SAMPLE LAYOUT – 4,000 S.F. W/ NO MULTI-PURPOSE ROOM



Design Elements

- Retail/ Logo Wall
- Inspiration Wall
- Manifesto Wall

REQUIRED AMENITIES

- Member Lobby
- Guest Lobby
- Manager's Office
- Cardio Area
- Strength Training Area
- Free Weight Area
- Utility/ Storage Room (1)
- Restroom(s) without Shower (1)
- Restrooms with Shower (2)
- Functional Area

OPTIONAL AMENITIES

- Trainer's Office


DESIGN HIGHLIGHTS

- Windows provide abundant natural light
- Shared double door entry promotes member engagement and accommodates equipment deliveries
- Guest Lobby
 - Defined by Manager's Office, Retail Logo Wall and Inspiration Wall
 - Clear line of site from Manager's Office
 - Member Lobby is screened from view
 - Free Weight Area is partially screened from view
- Retail Logo Wall immediately in front of guest door
- Cardio Area is immediately adjacent to front windows
- Free Weight Area is screened without being closed off
- Shared corridor for Restrooms and emergency exit
- Functional Area is anchored by a wall with high visibility to the main area of the club

RECOMMENDED CONFIGURATION AND REQUIRED ELEMENTS

SAMPLE LAYOUT – 4,000 S.F. W/ NO MULIT-PURPOSE ROOM

RECOMMENDED EQUIPMENT



This plan provides a 400 S.F. dedicated functional training area. The layout supports the minimal equipment package with room for optional pieces.



FINISHES & MATERIALS

Finishes & Materials

This section will provide a brief description of the finishes and materials that will be used throughout your club. Refer to your club specific Compliance Drawing (approved layout) to identify where the materials will be used in your club. See the Club Schemes section for material specifications.

PAINT

This is the main wall finish throughout the club. The high quality paint provides an affordable finish that brings life to the space through the use of color. There is a line of abuse-resistant paints available for high traffic areas. National account pricing makes the specified paint an exceptional value.

Paint must cure minimum 10 days with HVAC unit running prior to install any vinyl graphics to the wall. With HVAC unit not running, curing time for the paint is 15-20 days.

FLOORING – Refer to the “Non-Traditional Lease Space” section for additional requirements.

CARPET

Carpet tile is specified for aesthetics, recycled content, and reduced waste (when compared to broadloom) as well as ease of delivery, installation and replacement (when necessary). The carpet is loop weave, commercial grade and appropriately tough against the rigors of a health club. It comes with the manufacturer’s anti-microbial finish to inhibit growth of bacteria, reduce odors, and therefore extend the life of the carpet. When installed in accordance with manufacturer’s specifications, this product will provide many years use under cardio, strength, offices, and open floor areas. Your Compliance Drawing will provide complete details.

RUBBER FLOORING

This flooring is 100% recycled rubber and installed per manufacturer’s specifications for maximum durability and performance in the free weight area only.

ARTIFICIAL TURF

This is a durable product that can take a significant amount of abuse. The high quality top thread layer is easy to clean and adds to the support and cushion along with the rubber backing. For use in functional space only.

PORCELAIN TILE

This product has great durability, ease of maintenance and will likely last as long as the building. Proper installation per manufacturer’s specifications in addition to the use of industrial quality setting compounds and grouts are key. Using an epoxy grout is an investment and will stand the test of time and be resilient to stains and dirt. If epoxy is not in the budget for the whole job, it is highly recommended for showers and bathroom floors.

VINYL COMPOSITE TILE (VCT)

A cost effective alternate that provides a less durable option to tile. This product requires frequent maintenance including regular stripping, waxing and buffing.

FLOORING (continued)

VINYL PLANK FLOORING

This flooring is a cost-effective alternative to wood and is well-suited for use in multi-purpose rooms and stretching areas. Provide special care in areas where dumbbells and equipment may be used, since it does not offer the resilience of a cushion-backed wood floor. Install per manufacturer's specifications.

WOOD FLOORING

A cushion-backed wood floor is an alternative for the vinyl plank flooring. This product still requires maintenance. Install and maintain per manufacturer's specifications for a durable and aesthetically pleasing finish.

STAINED CONCRETE

A concrete floor can be cleaned and stained to add additional character to the space. If the existing concrete has been previously sealed or stained, it's difficult to change. However, a new or unsealed slab can benefit from staining.

Stained concrete can be utilized in place of carpet and tile in the main areas of the club and lobbies if the floor slab is new or reconditioned. The staining process colors the top portion of the concrete with a transparent dye. If the concrete has been patched and/or repaired the dye will not match the original concrete floor area resulting in an inconsistent and unacceptable finish. Staining a concrete slab is a multi-step process to ensure proper performance and durability. This includes proper preparation, slab densification, staining and sealant. Ensure your contractor is knowledgeable and experienced with the product and process, follows the manufacturer's recommendations and requirements. Stained concrete must be sealed on a regular basis to avoid wear and increase the usable life of the floor. Epoxy coatings, floor paint and other finishes are **NOT** allowed.

Required Concrete Stain Specifications:

Ameripolish 3D HS Densifier

Ameripolish SureLock Dye –

Color: Chocolate Brown

Ameripolish 3D SP Stain Protector

CONCRETE (STAINED) Floor Finish



FLOORING (continued)

MOISTURE TESTING

To ensure full warranties of all flooring materials, moisture testing of concrete is required prior to installation of all flooring materials. All flooring materials will need 48-72 hours of acclimation to the space prior to installing.

Refer to Vendor contacts listed in the color scheme section with any questions.

Moisture in concrete is not new. However, due to the industry's recent turn to moisture impervious products, it has now become an issue with trapping this moisture beneath the flooring products. In the past products have been "breathable" which allowed this moisture to escape into the air. The trapped moisture causes the adhesives to break down. There are two different ways to test for moisture vapor in concrete per the ASTM 2170 standard.


1. rH testing(Relative Humidity)

This test is done by drilling a hole into the concrete and inserting a probe into the concrete. After the designated time(usually 24-72 hours) you go back with a reader and check the rH levels at each probe. The probes will stay in the concrete and can be read for the life of the building. You would simply need the reader to go back and check for moisture in the future.

2. Calcium Chloride test.

This test is a specific kit made of calcium chloride pellets that are to be installed under a hood and kept free from being removed for 72hrs. Once the test is completed the pellets are weighed and noted. The pellets have taken on the moisture emitting from the concrete causing them to increase in weight. A specific formula will give you a reading.

- Both of these test should consist of 3 test for the first 1000 sq. ft. and an add another test for each additional 1000 sq. ft. thereafter. This will ensure complete coverage over the entire area to be installed.
- Most manufactures will accept the test results form both of these testing methods. Confirm with the flooring manufacture prior to testing.
- The rH method is the preferred method in the industry.
- A recommend testing kit for rH is the Wagner rH testing kit.



CULTURED STONE

This product is used at the retail logo wall to make a statement with its warmth and natural elegance that is intended to set-up the emotion of the space and visually support Anytime Fitness signage.

WALL COVERING

Wall covering, as specified, is an alternative for the cultured stone at the retail logo wall. Durable and aesthetically pleasing wall covering has been selected to accentuate components within the space. Install per manufacturer's specifications with appropriate edge detailing.

MIRRORS

Mirrors are required on two walls in the free weight area and a minimum of one wall in the multi-purpose room.

- Mirrors are 6' H, installed 2' above the finished floor with the top at 8'-0" AFF.
- Mirrors to run from corner to corner on each wall.
- All wall mirrors must have "J" channel on top and bottom.
- "J" channel to be used when a vertical end is not in a corner and exposed.
- Wall protection is strongly recommended below mirrors in the free weight area.

EQUIPMENT

- FRAMES: Platinum (Life Fitness), or Titanium Metallic (Precor)
- UPHOLSTERY: Slate (Life Fitness and Precor)
- Lower Profile Equipment is recommended, but not required
 - Life Fitness: Insignia series
 - Precor: Discovery series

CEILINGS & SOFFITS

CEILING PAINT

Using white paint for the exposed ceiling structure, is required, also known as an open ceiling design, is a great way to create an expansive and airy feel inside your club.

ACOUSTIC CEILING TILE (ACT)

ACT is a cost-effective system widely used in our industry. ACT is often installed to reduce the volume of a space by lowering the ceiling, reducing noise, and hiding aesthetics (duct-work, pipes, etc.). These products are frequently used in both guest and member lobbies, offices, and multi-purpose room.

ITEM	SPECIFICATION	NOTES
Ceiling Tile	USG ECLIPSE CLIMAPLUS SQ (White) 76575 2'x2'x3/4"	If ceiling tile is used in restroom alternate specification is required
Suspension System	USG DX / DXL 24 (White)	
Ceiling System Edge Trim	USG Compasso 12" Trim Elite (Flat White)	Curved trim is custom fabricated.

WALL PROTECTION

Wall protection is recommended in high traffic areas! There are two levels of potential damage and protection options.

Minimal Damage / Light Protection: This is damage to the painted surface that doesn't extend into the sheetrock; i.e. scuffs. etc. The protection options are abuse resistant paints. There are two levels of paint protection listed in the color scheme section of the design manual. Areas that typically benefit from light protection are hallways and multipurpose rooms.

Heavy Abuse / High Protection: This is the damage that penetrates the sheetrock. Areas that typically benefit from high protection are the free weights and functional areas. There are two high protection options.

1. Architectural Wood Panel – Recommended

- Recommended in Functional Area
- Recommended in Free Weight Area
- Furniture grade wood paneling that's both attractive and durable. These panels to be installed below and around mirrors.
- Refer to appendix for fabrication and installation requirements.

2. Metal Diamond Plate

- Coated metal plates that are durable. This material is limited to area below the mirrors in the free weight area.
- Diamond plate can **NOT** be used in any other area of the club and cannot extend higher than the bottom of the mirror.
- Due to the industrial look this material should be used sparingly.
- Refer to the appendix for installation requirements



DOORS

Preferred Vendor: Twin City Hardware (TCH)

Customer Service: 651-735-2200


bhaen@tchco.com

The materials used to finish your doors and windows vary greatly depending on the construction; – where they are located and how they are used. The selected finishes take into account aesthetics as well as durability and maintenance.

- Exterior storefront doors and windows are to match the existing and/or the remainder of the building. In the event of new construction a clear anodized aluminum system is preferred.
- The interior surface of hollow metal exterior emergency exit doors and frames should be painted to match the adjacent wall.
- Interior doors are to be flat/smooth solid core wood with a maple veneer, finished with a clear sealant.
 - Raised panel or hollow-core doors are **NOT** allowed.
- Frames are to be hollow metal – preferably welded – knock down metal frames are allowed
 - Wood frames are **NOT** allowed.
- Frame to be painted with a spray application and painted to match the adjacent wall
 - Brush and roller application are **NOT** allowed.

DOOR TYPES

WINDOW TYPES



- | | | | |
|-------------------|--------------------|----------------------|-----------------|
| • Restrooms | • Office | • Multi-Purpose Room | • Office Window |
| • Tanning/Message | • Trainer's Office | | |
| • Utility | | | |

FRAMES & HARDWARE

Preferred Vendor: Twin City Hardware (TCH)


Customer Service: 651-735-2200

bhaen@tchco.com

Lockable latch set to be Schlage ND73PD, with the following functions:

- When Locked by key, outside lever can only be unlocked by key. NO pin hole keys allowed
- Inside lever is always unlocked
- Push-button locking from inside
- Turn inside lever or close door to release button

FRAME TYPES



REFER TO 5/A7.1 AND
A4.0 FOR PAINTING
INSTRUCTIONS

HARDWARE GROUPS

GROUP #1

- BUTT HINGES
- 180 DEGREE HINGE ON SINGLE LEAF
- DESIGN HARDWARE Z-SD SINGLE DUMMY
- IVES RL32 ROLLER LATCH
- WALL MOUNT DOOR STOP HOLD OPEN
- DELTANA SOLID BRASS MAGNETIC
- DOOR STOP
- HOLDER EACH DOOR

GROUP #2

- BUTT HINGES
- WALL STOP
- CLOSER
- ND73PD LOCKSET
- KICKPLATE
- DOUBLE ROBE HOOK

GROUP #3

- BUTT HINGES
- WALL STOP
- OFFICE LOCKSET
- KICKPLATE
- DOUBLE ROBE HOOK

GROUP #4

- BUTT HINGES
- WALL STOP
- STORAGE LOCKSET
- KICKPLATE
- KICK DOWN HOLD OPEN

GROUP #5

- PANIC HARDWARE
- DETEX ALARM
- CONNECT TO SECURITY EQUIP.

GROUP #6

- PANIC HARDWARE - ELECTRIC STRIKE WITH REGULAR PANIC - PROVIDE NEW IF NOT EXISTING - G.C. TO PURCHASE THROUGH TWIN CITY HARDWARE (PREFERRED VENDOR) OR APPROVED EQUAL
- PULLS - PROVIDE IF NOT EXISTING
- REFER TO 8/A7.1





COLOR SCHEMES

Color Schemes

While design elements and finishes are designed to create brand recognition, we realize the importance of personal expression. To achieve this individuality Anytime Fitness has developed two distinct schemes for you to choose from: Elements & Gallery. These schemes create two very different environments through the use of color while maintaining consistency in materials and design elements. The following pages will provide the details for both schemes. It is important to note that the items are **NOT** interchangeable between the schemes.

The paint colors, finishes and materials within each scheme play a defined role and work in unison to create the overall design scheme. Paint colors cannot be added or eliminated from a scheme. Anytime Fitness will define the paint color for each wall within your club as part of the design process. The paint colors, along with floor finishes, will be specified on your approved layout known as the Compliance Drawing. Refer to the PROCESS section of this document for information on how to begin the design process. Do not start any work on your club, including paint, until you have an approved Compliance Drawing. Anytime Fitness has established a National Account Program with Sherwin Williams. All Anytime Fitness paint colors and specifications are stored in the Sherwin Williams national database, this program also provides a discount to our franchisees.

“It is widely recognized that colors have a strong impact on the human mood and emotions.”

– John F. Pile, Interior Design



Elements



Gallery



The diagrams and charts on the following pages provide call-outs for each design scheme. Refer to toilet room finishes and miscellaneous finishes for instructions specific to door finishes, mirrors, and workout equipment.

Elements Scheme



5,000 SQ.FT. – With MULTI-PURPOSE ROOM

ELEMENTS SCHEME

PAINT – Throughout Club - **Sherwin Williams National Account Number: 5753-1214-5**

KEY	MANUFACTURER	COLOR/NUMBER	SPECIFICATIONS
PL-1	Sherwin Williams	SW 7035 Aesthetic White	Paint: ProMar 200 Primer: Zero VOC B28W2600
PL-2	Sherwin Williams	SW 6711 Parakeet	Paint: ProMar 200 Primer: Zero VOC B28W2600
PL-3	Sherwin Williams	SW 6382 Ceremonial Gold	Paint: ProMar 200 Primer: Zero VOC B28W2600
PL-4	Sherwin Williams	SW 6642 Rhumba Orange	Paint: ProMar 200 Primer: Zero VOC B28W2600
PL-5	Sherwin Williams	SW 7522 Meadowlark	Paint: ProMar 200 Primer: Zero VOC B28W2600
PL-9	Sherwin Williams	7006 Extra White	Paint: ProMar 200 Primer: Zero VOC B28W2600
PL-10	Sherwin Williams	B42W00082 Eg-Shell White Waterborne Acrylic Dryfall	
PL-12	Sherwin Williams	“Anytime Purple” (Custom)	Paint: ProMar 200 Primer: Zero VOC B28W2600
PL-13	Sherwin Williams	SW 6258 Tricorn Black	Paint: ProMar 200 Primer: Zero VOC B28W2600
PDE-1	Sherwin Williams	Dry Erase Clear Gloss Coating KB65C2000 KIT	

Designated Vendor: Sherwin Williams – Patrick O’Brien

Customer Service: 440-263-1364 Patrick.w.obrien@Sherwin.com

Follow the manufacturer’s instructions regarding surface preparation and the use of proper primers to provide the best finish possible. Poor surface preparation and/or the use of incorrect primer will likely cost you time and money in requiring multiple coats to achieve the correct color. This will also increase the probability of low performance in maintaining and cleaning the surface. A minimum of one coat tinted primer and two eggshell finish coats are required.

Color-matching with brands other than Sherwin-Williams is NOT allowed

ADDITIONAL PAINT OPTIONS - Provides some extra durability to the wall.

Wall Protection Paint – GOOD (OPTIONAL): Sherwin Williams Industrial Pre-catalyzed Water-Based Epoxy K45W151 – Eggshell

Wall Protection Paint – BEST (OPTIONAL) Sherwin Williams Industrial Water-based Catalyzed Water-Based Epoxy 2 Part = Part A: B73W361 / Part B73V300 - Eggshell

ELEMENTS SCHEME

CARPET - Cardio, Strength Training, Offices

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
CA-1	Patcraft	00512 Exquisite	Dazzle Tile I0119 <u>Quarter-turn installation required</u>	
<u>Designated Vendor:</u> Shaw Integrated Solutions (S.I.S.) Customer Service: 800-338-9479 anytime.fitness@shawinc.com				

RUBBER - Free Weights

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
RF-1	Ecore	EL09 Pumpin' Purple	Everlast Roll	
<u>Designated Vendor:</u> Ecore International, Inc. Customer Service: 515-450-2144 matt.koch@ecoreintl.com				

CUSHIONED TURF - Functional Area

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
TURF	Ecore	LMNT - 000218 Laminate L1 Better Purple	Custom	
Designated Vendor: Ecore International, Inc. Customer Service: 515-450-2144 matt.koch@ecoreintl.com				

STAINED CONCRETE - Cardio, Strength Training, Member & Guest Lobby

	MANUFACTURER	COLOR/ NUMBER	SAMPLE
STC	Ameripolish	Ameripolish 3D HS Densifier Ameripolish SureLock Dye Color: Chocolate Brown Ameripolish 3D SP Stain Protector CONCRETE (STAINED) Floor Finish	
<u>Designated Vendor:</u> Contractor to source locally			

ELEMENTS SCHEME

PORCELAIN TILE - Member & Guest Lobbies, Toilet/Shower Rooms, and Tanning

	LOCATION	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
T-1 Tile	Floors in Guest Lobby and Member Lobby	Daltile	CS55 Moroccan Brown	Continental Slate Series 12" x12" (#12121P6)	
T-1 Grout		Marpi Keracolor	#11 Sahara Beige	Sanded Grout 	
T-2 Tile	Restroom Floors (See T-4 for Shower floors)	Daltile	CS55 Moroccan Brown	Continental Slate Series 12" x12" (#12121P6)	
T-2 Grout		Marpi Keracolor	#11 Sahara Beige	Sanded Grout 	
T-2 Base	Restroom and Showers	Daltile		Cove Base Tile (Required) - 6" x 12" (S36C9T1P2) - 1" x 6" (SC36C9T1P2)	
T-3 Tile	Toilet/ Shower Walls	Daltile	EV98 Terrace Beige	Esta Villa Series Wall Field Tile 10" x 14" (EV9810141P2)	
CRN-1	Corner for Bullnose	Daltile	EV98 TB	3x3 Corner	
T-3 Grout		Marpi Keracolor	#39 Ivory	Sanded Grout 	
T-3 Cap	Bullnose for Restroom Walls	Daltile		Bullnose Tile (Required) - 3" x10" (EV9810141P) - Installed w/ "Brick Works Pattern"	
T-4 Tile	Shower Floors	Daltile	CS55 Moroccan Brown	Continental Slate Series Floor Field Tile 3" x 3" (33MSC1P)	
T-4 Grout		Marpi Keracolor	#11 Sahara Beige	Sanded Grout 	
Designated Vendor: Shaw Integrated Solutions (S.I.S.) Customer Service: 800-338-9479 anytime.fitness@shawinc.com					

SEE "APPENDIX" FOR MORE INFORMATION & DETAILS

ELEMENTS SCHEME


VINYL COMPOSITE TILE Member & Guest Lobby, Tanning ALTERNATE for specified tile

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
VCT-1	Armstrong	Color: 52149 Cocoa Brown	Excelon Stonetex	
Flooring must be sourced through an Armstrong flooring contractor or local dealer: www.armstrongflooring.com/commercial/en-us/contact-us.html				

VINYL PLANK FLOORING Multi-Purpose Room

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
VP-1	Patcraft	1600V Color :820 Spiced Cherry	Click Refresh Do not use and pad when installing	
Designated Vendor: Shaw Integrated Solutions (S.I.S.) Customer Service: 800-338-9479 anytime.fitness@shawinc.com				

WOOD FLOORING Multi-Purpose Room ALTERNATE for Vinyl Plank

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
WF-1	Junckers Sport & Dance Floor Systems	Clip System 9/16" Sylva Red (3/16" foam underlay) Satin	Activity Floor	
Designated Vendor: Shaw Integrated Solutions (S.I.S.) Customer Service: 800-338-9479 anytime.fitness@shawinc.com				

WALL PROTECTION Functional Area

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
WP-1	Wood paneling to be manufactured by millwork fabricator.	Maple Finish Color: Clear	Natural Wood Panel	
<u>Preferred Vendor:</u> Global Retail Environments (GRE) Customer Service: 763-856-0217 jscharber@globalretailenvironments.com				

SEE "APPENDIX" FOR MORE INFORMATION & DETAILS

ELEMENTS SCHEME

CULTURED STONE - Retail Logo Wall

CULTURED STONE - Retail Logo Wall				
	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
ST-1	Boral	Mohave	Pro-Fit Ledgestone Flats Pro-Fit Ledgestone Corners	
Designated Vendor: Shaw Integrated Solutions (S.I.S.) Customer Service: 800-338-9479 anytime.fitness@shawinc.com				

Wall Covering - Retail Logo Wall – Alternate for Cultured Stone

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
WC-1	Lanark	MS-710-02 Mocha Java Use this specific # for preferred pricing.	Bungalow	
<u>Preferred Vendor:</u> TRI-KES Customer Service: 800-200-8120				

MANIFESTO WALL

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
G-1	Archetype	Manifesto Graphic Refer to Anytime Fitness signage style guide for details.	Wall is painted “Anytime Purple”	
Designated Vendor: Archetype Customer Service: 888-512-1272 customerservice@archetypeesign.com				

VINYL BASE – Used at all walls, excluding restrooms

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
VB-1	Johnsonite	40 - Black	6" Vinyl Cove Base	
Preferred Vendor: Shaw Integrated Solutions (S.I.S.) Customer Service: 800-338-9479 anytime.fitness@shawinc.com				

SEE "APPENDIX" FOR MORE INFORMATION & DETAILS

ELEMENTS SCHEME

VINYL FLOORING TRANSITION STRIP – To be used between all flooring material changes

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
TS-1	Johnsonite	CE-40-C Black	12' "T" Molding Transition 12' Flex Track – MTC-00-A	
Designated Vendor: Shaw Integrated Solutions (S.I.S.) Customer Service: 800-338-9479 anytime.fitness@shawinc.com				

MERCHANDISING INSERT - Retail Logo Wall

	MANUFACTURER	COLOR/ NUMBER	IMPORTANT	SAMPLE
MU-1	Global Retail Environments	Prefabricated clear maple wood merchandising insert.	Glass shelves and mirror not included (Contractor to source locally)	
Designated Vendor: Global Retail Environments (GRE) Customer Service: 763-856-0217 jscharber@globalretailenvironments.com				

DOORS, FRAMES & HARDWARE – Interior Doors & Windows

	MANUFACTURER	COLOR/ NUMBER	Important	SAMPLE
Doors	Twin City Hardware	Sealed clear maple Solid core commercial grade w/ metal knock down frames with hardware	Glass not included (When applicable) (Contractor to source locally)	
Preferred Vendor: Twin City Hardware (TCH) Customer Service: 651-735-2200 bhaen@tchco.com				

WALL MIRRORS– Free Weight Area & Multi-Purpose Room

	MANUFACTURER	COLOR/ NUMBER	Important	SAMPLE
Mirrors	The Mirror Company		Wall Protection goes under mirrors	
Preferred Vendor: The Mirror Company Customer Service: 800-473-0619 dave@themirrorcompany.com				

SEE "APPENDIX" FOR MORE INFORMATION & DETAILS

Gallery Scheme



5,000 SQ.FT. – With MULTI-PURPOSE ROOM

GALLERY SCHEME

PAINT – Throughout Club - **Sherwin Williams National Account Number: 5753-1214-5**

KEY	MANUFACTURER	COLOR/NUMBER	STYLE
PG-1	Sherwin Williams	SW 7014 Eider White	Paint: ProMar 200 Primer: Zero VOC B28W2600
PG-2	Sherwin Williams	SW 6492 Jetstream	Paint: ProMar 200 Primer: Zero VOC B28W2600
PG-3	Sherwin Williams	SW 6711 Parakeet	Paint: ProMar 200 Primer: Zero VOC B28W2600
PG-4	Sherwin Williams	SW 6558 Plummy	Paint: ProMar 200 Primer: Zero VOC B28W2600
PG-5	Sherwin Williams	SW 7674 Peppercorn	Paint: ProMar 200 Primer: Zero VOC B28W2600
PG-9	Sherwin Williams	7006 Extra White	Paint: ProMar 200 Primer: Zero VOC B28W2600
PG-10	Sherwin Williams	B42W00082 Eg-Shell White Waterborne Acrylic Dryfall	
PG-12	Sherwin Williams	“Anytime Purple” (Custom)	Paint: ProMar 200 Primer: Zero VOC B28W2600
PG-13	Sherwin Williams	SW 6258 Tricorn Black	Paint: ProMar 200 Primer: Zero VOC B28W2600
PDE-1	Sherwin Williams	Dry Erase Clear Gloss Coating KB65C2000 KIT	

Designated Vendor: Sherwin Williams – Patrick O’Brien

Customer Service: 440-263-1364 Patrick.w.obrien@Sherwin.com

Follow the manufacturer’s instructions regarding surface preparation and the use of proper primers to provide the best finish possible. Poor surface preparation and/or the use of incorrect primer will likely cost you time and money in requiring multiple coats to achieve the correct color. This will also increase the probability of low performance in maintaining and cleaning the surface. A minimum of one coat tinted primer and two eggshell finish coats are required.

Color-matching with brands other than Sherwin-Williams is NOT allowed

ADDITIONAL PAINT OPTIONS - Provides some extra durability to the wall.

Wall Protection Paint – GOOD (OPTIONAL): Sherwin Williams Industrial Pre-catalyzed Water-Based Epoxy K45W151 – Eggshell

Wall Protection Paint – BEST (OPTIONAL) Sherwin Williams Industrial Water-based Catalyzed Water-Based Epoxy 2 Part = Part A: B73W361 / Part B73V300 - Eggshell

GALLERY SCHEME

CARPET - Cardio, Strength Training, Offices

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
CA-1	Patcraft	AF Gallery Custom	Dazzle Custom <u>Quarter-turn installation required</u>	
<u>Designated Vendor:</u> Shaw Integrated Solutions (S.I.S.) Customer Service: 800-338-9479 anytime.fitness@shawinc.com				

RUBBER - Free Weights

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
RF-1	Ecore	EL09 Pumpin' Purple	Everlast Roll	
Designated Vendor: Ecore International, Inc. Customer Service: 515-450-2144 matt.koch@ecoreintl.com				

CUSHIONED TURF - Functional Area

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
TURF	Ecore	LMNT - 000218 Laminate L1 Better Purple	Custom	
Designated Vendor: Ecore International, Inc. Customer Service: 515-450-2144 matt.koch@ecoreintl.com				

STAINED CONCRETE - Cardio, Strength Training, Member & Guest Lobby

	MANUFACTURER	COLOR/ NUMBER	SAMPLE
STC	Ameripolish	Ameripolish 3D HS Densifier Ameripolish SureLock Dye Color: Chocolate Brown Ameripolish 3D SP Stain Protector CONCRETE (STAINED) Floor Finish	
Recommended Vendor: Contractor to source locally			

ELEMENTS SCHEME

PORCELAIN TILE - Member & Guest Lobbies, Toilet/Shower Rooms, and Tanning

	LOCATION	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
T-1 Tile	Floors in Guest Lobby and Member Lobby	Daltile	CS55 Moroccan Brown	Continental Slate Series 12" x12" (#12121P6)	
T-1 Grout		Marpi Keracolor	#11 Sahara Beige	Sanded Grout 	
T-2 Tile	Restroom Floors (See T-4 for Shower floors)	Daltile	CS55 Moroccan Brown	Continental Slate Series 12" x12" (#12121P6)	
T-2 Grout		Marpi Keracolor	#11 Sahara Beige	Sanded Grout 	
T-2 Base	Restroom and Showers	Daltile		Cove Base Tile (Required) - 6" x 12" (S36C9T1P2) - 1" x 6" (SC36C9T1P2)	
T-3 Tile	Toilet/ Shower Walls	Daltile	EV98 Terrace Beige	Esta Villa Series Wall Field Tile 10" x 14" (EV9810141P2)	
CRN-1	Corner for Bullnose	Daltile	EV98 TB	3x3 Corner	
T-3 Grout		Marpi Keracolor	#39 Ivory	Sanded Grout 	
T-3 Cap	Bullnose for Restroom Walls	Daltile		Bullnose Tile (Required) - 3" x10" (EV9810141P) - Installed w/ "Brick Works Pattern"	
T-4 Tile	Shower Floors	Daltile	CS55 Moroccan Brown	Continental Slate Series Floor Field Tile 3" x 3" (33MSC1P)	
T-4 Grout		Marpi Keracolor	#11 Sahara Beige	Sanded Grout 	

Designated Vendor: Shaw Integrated Solutions (S.I.S.)

Customer Service: 800-338-9479

anytime.fitness@shawinc.com

SEE "APPENDIX" FOR MORE INFORMATION & DETAILS

GALLERY SCHEME


VINYL COMPOSITE TILE Member & Guest Lobby, Tanning ALTERNATE for specified tile

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
VCT-1	Armstrong	Color: 52147 Pumice Stone	Excelon Stonetex	
Flooring must be sourced through an Armstrong flooring contractor or local dealer: www.armstrongflooring.com/commercial/en-us/contact-us.html				

VINYL PLANK FLOORING Multi-Purpose Room

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
VP-1	Patcraft	1600V Color :820 Spiced Cherry	Click Refresh Do not use any pad when installing	
Designated Vendor: Shaw Integrated Solutions (S.I.S) Customer Service: 800-338-9479 anytime.fitness@shawinc.com				

WOOD FLOORING Multi-Purpose Room ALTERNATE for Vinyl Plank

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
WF-1	Junckers Sport & Dance Floor Systems	Clip System 9/16" Sylva Red (3/16" foam underlay) Satin	Activity Floor	
Designated Vendor: Shaw Integrated Solutions (S.I.S.) Customer Service: 800-338-9479 anytime.fitness@shawinc.com				

WALL PROTECTION Functional Area

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
WP-1	Wood paneling to be manufactured by millwork fabricator.	Maple Finish Color: Clear	Natural Wood Panel	
Preferred Vendor: Global Retail Environments (GRE) Customer Service: 763-856-0217 jscharber@globalretailenvironments.com				

SEE "APPENDIX" FOR MORE INFORMATION & DETAILS

GALLERY SCHEME

CULTURED STONE - Retail Logo Wall

CULTURED STONE - Retail Logo Wall				
	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
ST-1	Boral	Platinum	Pro-Fit Ledgestone Flats Pro-Fit Ledgestone Corners	
Designated Vendor: Shaw Integrated Solutions (S.I.S.) Customer Service: 800-338-9479 anytime.fitness@shawinc.com				

Wall Covering - Retail Logo Wall – Alternate for Cultured Stone

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
WC-1	Lanark	MS-710-02 Mocha Java Use this specific # for preferred pricing.	Bungalow	
<u>Preferred Vendor:</u> TRI-KES Customer Service: 800-200-8120				

MANIFESTO WALL

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
G-1	Archetype	Manifesto Graphic Refer to Anytime Fitness signage style guide for details.	Wall is painted “Anytime Purple”	
Designated Vendor: Archetype Customer Service: 888-512-1272 customerservice@archetypesign.com				

VINYL BASE

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
VB-1	Johnsonite	40 - Black	6" Vinyl Cove Base	
Designated Vendor: Shaw Integrated Solutions (S.I.S.) Customer Service: 800-338-9479 anytime.fitness@shawinc.com				

SEE "APPENDIX" FOR MORE INFORMATION & DETAILS

GALLERY SCHEME

VINYL FLOORING TRANSITION STRIP

	MANUFACTURER	COLOR/ NUMBER	STYLE	SAMPLE
TS-1	Johnsonite	CE-40-C Black	12' "T" Molding Transition 12' Flex Track – MTC-00-A	
Designated Vendor: Shaw Integrated Solutions (S.I.S.) Customer Service: 800-338-9479 anytime.fitness@shawinc.com				

MERCHANDISING INSERT - Retail Logo Wall

	MANUFACTURER	COLOR/ NUMBER	IMPORTANT	SAMPLE
MU-1	Global Retail Environments	Prefabricated clear maple wood merchandising insert.	Glass shelves and mirror not included (Contractor to source locally)	
Designated Vendor: Global Retail Environments (GRE) Customer Service: 763-856-0217 jscharber@globalretailenvironments.com				


DOORS, FRAMES & HARDWARE – Interior Doors & Windows

	MANUFACTURER	COLOR/ NUMBER	Important	SAMPLE
Doors	Twin City Hardware	Sealed clear maple Solid core commercial grade w/ metal knock down frames with hardware	Glass not included (When applicable) (Contractor to source locally)	
Preferred Vendor: Twin City Hardware (TCH) Customer Service: 651-735-2200 bhaen@tchco.com				

WALL MIRRORS– Free Weight Area & Multi-Purpose Room

	MANUFACTURER	COLOR/ NUMBER	Important	SAMPLE
Mirrors	The Mirror Company		Wall Protection goes under mirrors	
<u>Preferred Vendor:</u> The Mirror Company Customer Service: 800-473-0619 dave@themirrorcompany.com				

SEE "APPENDIX" FOR MORE INFORMATION & DETAILS



INTERIOR FIXTURES
& ACCESSORIES

Interior Fixtures & Accessories

LIGHTING

The Lighting of your club should include practical, general lighting with a few highlighted elements. Many spaces will already be equipped with general lighting, but keep in mind that your layout may require some alterations. To ensure that all spaces are receiving the appropriate amount of lighting, some relocated and/or supplemental lighting may be necessary. Decorative fixtures (track-required) are used to punctuate certain architectural elements of your club.

GENERAL LIGHTING

Preferred Vendor: Villa Lighting

Customer Service: 314-633-0532

adam.carrier@villalighting.com

GENERAL CLUB LIGHTING

- Provide LED linear fixtures, evenly spaced, in area without ceilings. High bay style light fixtures should not be used unless the ceiling height is the appropriate height (typically 30+ feet) and have the appropriate diffusers.
- Provide 2' x 2' LED lay-in fixtures, evenly spaced, in areas with acoustic ceilings
- Verify that proper light levels are met
 - Your electrician must provide or maintain a consistent lighting level of 50 to 60 foot-candles at workout and office areas.
- For clubs reusing existing lighting:
 - Remove or relocate any fixtures (as needed) to provide proper light levels to new or reconfigured rooms or spaces
 - Replace existing bulbs with “cool white” bulbs for consistency in light level and quality
 - Encouraged to explore LED change over options from existing lighting. Check with your local energy company for possible rebates.

TRACK LIGHTING

- Installed in front of Retail Logo Wall, Manifesto wall and A-Fit Nation wall.
- Position track to evenly illuminate full height of the walls
- Four(4) track heads per each wall location
- Finish to be white track and heads at white ceiling
- Mounted from acoustic ceiling (recommended) or from exposed roof deck (if applicable)
- Recommend track height is 10'-0" A.F.F.

OFFICE LIGHTING

- Provide 2' x 2' LED lay-in fixtures, evenly spaced, in areas with acoustic ceilings to achieve appropriate light levels (as required)

MASSAGE/ TANNING ROOM LIGHTING

- Provide 2' x 2' LED lay-in fixtures, evenly spaced, in areas with acoustic ceilings to achieve appropriate light levels (as required)

LIGHTING

TOILET/SHOWER ROOM LIGHTING

- Install one to two recessed lights into ceiling
- Install wall sconces on either side of mirrors, if desired
- Install waterproof light fixture in the shower

UTILITY ROOM LIGHTING

- Install one surface mounted light onto ceiling

ENVIRONMENTALLY FRIENDLY INFORMATION

T-5 fluorescent lamps are a great alternative to T-8 and T-12 lamps. The color rendition and output are superior, which means you could potentially reduce the number of fixtures required when determining the lighting calculations. The cost of T-5 lamps can sometimes range from 3-5 times more expensive than the others, but you will save in fixture and electricity costs over the lifetime of the lights, which are typically rated for 20,000 hours.

- Motion detection lighting can reduce operating costs in some rooms, such as the restrooms. Motion sensor lighting is **NOT** allowed in general areas.

LED LIGHTING

LED's (Light Emitting Diodes) are the latest and most exciting technological advancement in the lighting industry. LEDs are small, solid light bulbs which are extremely energy efficient and long lasting. LEDs operate differently than traditional incandescent and fluorescent light bulbs. This makes LEDs far more rugged and durable than traditional light bulbs. LED technology also offers many additional advantages over incandescent, neon and compact fluorescent lighting devices.

LED Features and Benefits:

- Saves Energy; LED lights use 50-90% less power than traditional lighting
- Saves money; lowers energy bills
- Saves the environment; less waste and disposal hazards
- Extremely long life lasts 4-5 times longer than traditional lighting.
- Reduced maintenance costs; Replacement cycle costs are drastically reduced.
- Reduces ambient heat; generates far less heat than traditional lighting allowing greater savings on air conditioning costs.
- Produces less glare; higher productivity and safety in the work place.
- Better directional lighting; directionality allows for precision lighting with no wasted light.
- Less pollution: No toxic chemicals like that found in traditional incandescent, fluorescent and HID lighting like- arsenic, mercury, lead, carbon dioxide or phosphorous.
- No UV radiation produces no ultra violet or infrared light.
- LED's are also recyclable and considered "green" or Earth-Friendly.
- Possible rebates from your local energy company



MEMBER LOBBY - FURNITURE & COMPONENTS

The Member Lobby has 2 main functions; storage for personal items and a place to change shoes and prepare for a workout. The Member Lobby should include the following:

- Coat storage
- Storage for personal items; keys, phone, clothes, gym bag, etc.
- Place to change shoes

Things To Remember

- The space should be a min. of 10' x 10' to allow for adequate circulation between cubbies and benches
- It is typically located next to the Manager's Office to allow for member/manager interaction and engagement
- Fixtures should be maple to match the doors, signage and other wood items in the club
- Adding legs to elevate the cubbies, provides space underneath for shoe storage
- Do not locate emergency lights, cameras, vents or any other items on the wall that is to receive The 'AFIT NATION' graphic.
- Wood cubbies provide a welcoming and inviting, non-locker room atmosphere. Steel lockers are not permitted. If you feel added security is required, locker inserts are available for the cubbies.
- Vending machines are optional and may be located in the member lobby
- 911 phone & defibrillator may be located in the member lobby
- We recommend that you request your GC to include furniture assembly in their bid



MEMBER LOBBY - FURNITURE & COMPONENTS

MEMBER LOBBY BENCH - **A**

- Located in or near member lobby
- Finish: Clear maple with black seat top
- Size: 18" wide x 18" high x 36" long

Preferred Vendor: Global Retail Environments (GRE)

Customer Service: 763-856-0217

jscharber@globalretailenvironments.com



MEMBER STORAGE CUBBIES – **B**

OPTION 1 - IKEA

- Located in the Member Lobby
- IKEA Kallax | ARTICLE NUMBER: 003.601.44
- Finish: "Walnut effect light gray"
- Size: 57-7/8" wide x 57-7/8" high x 15-3/8" deep
- Recommend to install metal legs to bottom of unit to raise off the ground for shoe storage beneath
- Does not include locker inserts – can be purchased separately through GRE
- Does not include coat rod – source locally



MEMBER STORAGE CUBBIES – **B**

OPTION 2 – GRE COMBO UNIT – includes **B&C**

- Located in the Member Lobby
- Wood grain plastic laminate cubbies/lockers on elevated stand with boot tray
- Unit Size: 59.75" wide x 69.75" high x 15.75" deep
- Includes: 9 open cubbies, 4 (1) door locking units, 1 (4) door locking unit, 3' hanging coat rod, 2 end cubbies, elevated steel base & boot tray

Preferred Vendor: Global Retail Environments (GRE)

Customer Service: 763-856-0217

jscharber@globalretailenvironments.com



MEMBER LOBBY - FURNITURE & COMPONENTS

CUBBIE 1 DOOR LOCKER INSERT – C

- Optional Cubbie Enhancement
- Located in the Member Lobby
- Material: Wood grain plastic laminate
- Fits both IKEA cubbies and GRE Combo Unit
- 4 – 1 door locker inserts are included in GRE's Combo Unit
- Must purchase separately if using IKEA cubbies
- Lockable inserts – keys are only removable in the locked position & are numbered to match corresponding locker number – all keys are master keyed

Preferred Vendor: Global Retail Environments (GRE)



CUBBIE 4 DOOR LOCKER INSERT – C

- See description above for 1 Door Locker Insert (same, but divided into 4 lockable compartments)
- 1 – 4 door locker insert included in GRE's Combo Unit
- Must purchase separately if using IKEA cubbies
- Great space saving option for keys, wallets & cell phones

Preferred Vendor: Global Retail Environments (GRE)

Customer Service: 763-856-0217

jscharber@globalretailenvironments.com



COAT ROD - D

- Located between storage cubbies and adjacent wall in member lobby
- Size: 36" long
- Sourced locally if using IKEA cubbies
- Included in GRE's Combo Unit





GUEST LOBBY - FURNITURE & COMPONENTS

The Guest Lobby creates the first impression for potential members and is the start to each member workout. It is located directly inside the main door(s). The Guest Lobby has 3 main functions; it offers a welcoming, unimposing first impression, it sets the tone of the club (club culture), and it serves as a waiting area.

Things To Remember

- The Inspiration Wall is located to the side of the door(s) and screens equipment while still providing a view into the club. It also helps to establish your club culture and member interaction. It needs to remain open and visible. Do not place any furniture in front of the Inspiration Wall.
- The Retail Logo Wall is located on the wall opposite the door(s). You are not required to merchandise product, but if you do, it's important to keep it organized, relevant, and uncluttered.
- We recommend a minimal amount of furniture, as most people aren't waiting for extended periods of time and it's important to maintain an uncluttered lobby with adequate circulation. We recommend 2 chairs and a high top table, which works great for a brief conversations.
- Be sure any wood furniture matches the clear maple finish of the doors, signage and other wood items in the club.
- Guest Lobby furniture can be sourced locally.



EQUIPMENT

WORKOUT EQUIPMENT (provide as required per the equipment list in the academy)

- It is required that you work directly with one of our two preferred vendors for the main equipment in your club.
- Franchisees opening their first club must follow the equipment guides defined in the equipment matrix and other supporting documentation.
- Equipment, including functional equipment systems, are available through a series of approved vendors listed on the Vendor Portal.

Designated Vendor: Life Fitness
Customer Service: 208-660-7132
thomas.ouren@lifefitness.com

Designated Vendor: Precor
Customer Service: 425-482-5490
anytimefitness@precor.com

REUPHOLSTERY

- It is recommended to find a local upholstery company that can order from Boltaflex, the brand standard upholstery, and recover your current pads.

Designated Vendors: Life Fitness
Customer Service: 208-660-7132
Slate | 363771 Boltaflex Colorguard 2000 | MFG-Part # 36377100

Designated Vendors: Precor
Customer Service: 914-213-2112
Slate | CW39085-101

TANNING EQUIPMENT (if applicable)

- Tanning Rooms, and associated tanning bed operations, must comply with all requirements as-directed by your state tanning regulatory agency.
- Contact your state tanning regulatory agency to verify floor finish specified in Section 2 complies with their flooring requirements.

Designated Vendor: PC Tan
Customer Service: 800-327-8826
paulm@pctan.com

Designated Vendor: Pro Sun International
Customer Service: 727-825-0400 x 224
jenniferh@prosun.com

HYDRO MASSAGE EQUIPMENT (if applicable)

Designated Vendor: Hydro Massage
Customer Service: 800-699-1008
info@hydromassage.com

Designated Vendor: Pro Sun International -
AquaFrixio
Customer Service: 727-825-0400 x 224
jenniferh@prosun.com

SEE "BUILDING SYSTEMS" FOR
DATA AND POWER REQUIREMENTS

ACCESSORIES

TOILET/SHOWER ROOMS

- Provide shelf in showers for toiletries.
- Provide and install a mirror above the sink and be sure the height meets local building codes for handicap accessible toilet/shower room(s).
- Provide and install a towel bar or hook outside shower stall.
- Provide and install hook(s) behind door, if desired.
- Provide and install door closures.
- Provide a bench or chair, if desired, and be sure they do not block the clear area required in handicap accessible toilet/shower room(s). (Source Locally)
- Provide and install a full-length mirror, if desired. (Source Locally)

Preferred Vendor: Twin City Hardware (TCH)

Customer Service: 651-735-2200

bhaen@tchco.com

TANNING ROOMS (If applicable)

- Provide and install a paper towel dispenser, as customers will be required to clean the tanning bed before and after each use.
- Provide and install a shelf or provide a table large enough for a spray bottle of cleaner/disinfectant for use in cleaning the bed.
- Provide and install a full-length mirror, if desired.
- Provide and install hook(s) behind door, if desired.
- Provide a chair or bench, if desired.
- Provide a fan if desired.

VENDING MACHINE (if applicable)

- One vending machine that sells bottled items is recommended in or near the member lobby.
- Vending machines should not be visible from the main entrance/guest lobby.
- Contact your local Pepsi or Coke distributor, they will likely install a machine at no cost to you, and keep it stocked.
- Required a standard 110V Outlet.

Preferred Vendor: VendTek

Customer Service: 800-207-7763 ext. 107

tomst@vendtek.com

SEE "BUILDING SYSTEMS" FOR POWER REQUIREMENTS

ACCESSORIES

HAND DRYERS (recommended)

- XLERATOR hand dryer, one for each restroom.
- Stainless steel recess kit is required to meet ADA code.

Preferred Vendor: Zogics

Customer Service: 888-623-0088 x 101

jeff@zogics.com



WORKOUT FLOOR (recommended)

- Provide a minimum of two “gym wipes” dispensers.
 - If you select the wall-mount style, one dispenser should be mounted with bottom of dispenser no higher than 48” from the floor.
- Provide one “Simplehuman” trash can below or next to each “gym wipes” station.
 - Simplehuman Smartbucket 40-Liter semi-round step-on trash can available at Bed, Bath & Beyond.

Preferred Vendor: Gym Wipes by 2XL

Customer Service: 703-356-1256

sales@sxllcorp.com

Preferred Vendor: Staples

Customer Service: 651-234-4109

Kevin.hoff@staples.com

Preferred Vendor: Wipes.com

Customer Service: 877-348-9473

sales@wipes.com

Preferred Vendor: Zogics

Customer Service: 888-623-0088 x 101

jeff@zogics.com

AIR FRAGRANCE SYSTEM

Be sure your club maintains a clean, fresh smell at all times. Current and potential members **MUST** be provided an environment that is pleasing to all senses.

- Provide staff with a method of deodorizing the workout areas of the club at regular intervals.
- Provide each toilet and tanning room with air freshener (automatic or manual).

Preferred Vendor: Scent Air

Customer Service: 704-792-7560

srsmith@scentair.com

ACCESSORIES

WINDOW SHADES

Windows are a great attribute for any club. They add to the open spacious feeling and enhance the member experience, however they can present challenges. Heat gain and blinding light are problems that can arise. Fortunately these are temporary problems that can be easily managed. In most cases the problems occur for a limited period of time during the day and can even be seasonal. Window shades are a great solution to address the variability of the problem. Shades can be lowered and raised to address the problem as it occurs. Whereas materials such as glass tinting and graphics are permanent. They work well during excessive sunlight hours but are overkill and unnecessary the majority of the time. This is especially important at night when the light for the windows helps to communicate our ALWAYS OPEN - 24/7 access. We have partnered with a national vendor to provide a high quality, commercial grade shade for our franchisees at an affordable price.

- It is recommended to provide blinds for all main office windows to ensure people cannot view the security monitors after hours.

Roll-A-Shade Architectural Specifications:

- Material: Material to be 4000 Granite 5% density.
- Internal Hembar: Fabric wrapped bottom weight bar.
- Control System: Adjustment free system shall be provided by stainless steel chain inside the clutch system.
- All components that do not have bronze mullion: Clutch, brackets, child safety tension device all to be grey.
- All components with a bronze mullion: Bronze child safety tension device; clutch and brackets to be black.
- Branding of window shades is **NOT** allowed.

Preferred Vendor: Roll-A-Shade

Customer Service: 951-245-5077 x 138

Andrew.Stricklin@rollashade.com

The material specified was selected to allow some light to enter while blocking the excess majority. In extreme cases a heavier/darker weave may be required. The vendor representative can assist with the alternate materials in those rare cases.



BUILDING SYSTEMS

Building Systems

The following information provides minimum guidelines for your mechanical, electrical, and plumbing systems of your club. All clubs are slightly different, so verify your specific needs with your general contractor and building official PRIOR to design and construction.

MECHANICAL

GENERAL HVAC

- System Recommendation Minimum: 1 ton per 350 sq.ft. (or as required by code). All visible ductwork in an open exposed ceiling **MUST** be spiral duct work.



CEILING FAN(S)

- Provides circulation and cooling for the workout areas.
- Standard 52" commercial grade ceiling fans are recommended.
 - Color: White
 - An average 5,000 sq. ft. club would typically use 6-8 52" fans.
- Macro Air Fan – 12'
 - Color: Milled aluminum finish.
 - An average 5,000 sq. ft. club would typically use one 12' diameter fan.

Preferred Vendor: Villa Lighting

Customer Service: 314-633-0532

adam.carrier@villalighting.com

- Large, high-output fan(s) may be considered as an alternative for clubs with ceilings higher than 12'.
 - Color: Milled aluminum finish.
 - An average 5,000 sq. ft. club would typically use one 12' diameter fan.
 - If desired, the Running Man logo is available on some models.

Preferred Vendor: Big Ass Solutions

Customer Service: 859-629-7548

pete.nuckols@bigasssolutions.com

DROP FAN

- Recommend for Multi-Purpose Rooms to circulate air and cool the room.
- Fits in to standard 2' x 2' ACT ceiling grid.
- Remote control operation.

Preferred Vendor: Drop Fan

Customer Service: 844-376-7326

support@dropfan.com

ELECTRICAL

SERVICE

- 400 AMP, 120/208V, 3-Phase, 4 Wire.

GENERAL

- Electrical outlets should be installed every 10 feet at standard height along all walls, or as dictated by your local electrical code.
- Provide outlets in the ceiling for televisions. Each TV will require 2 outlets – one for the TV and one for the receiver.
 - Outlet locations will be based on the final cardio equipment layout.
 - Coordinate with data requirements.
 - **NO** exposed conduit is allowed.
- Provide power for ceiling fan(s).
 - Coordinate with mechanical.
- Provide dedicated outlets for cardio equipment (i.e. treadmills), if indicated.
 - Each piece of equipment will require its own 110V, 20 AMP circuit.
 - Specify the outlets as separate 110V circuits and coordinate with your general contractor.
 - Verify power requirements with the equipment vendor.
 - Coordinate with data requirements.
 - Power Supply Options:
 1. Run the power in the floor by trenching through existing concrete slab (recommended).
 2. Low profile, metal raceway. (Legrand AL5200 Multi-Channel)
 3. Run the wiring down a load-bearing column, wires and conduit to be concealed.
- Provide additional outlets if you have LCD screens on your cardio equipment.
 - Verify power requirements with the equipment vendor.
 - Coordinate with data requirements.

MEMBER LOBBY

- Provide one duplex 110V outlet above member entrance door(s).
 - This outlet will be used by the electronic door strike and the access control system.
 - Coordinate with security requirements.
- Provide a dedicated outlet for vending machine(s), if desired, based on the specific power requirements.
 - Refer to section 4 for equipment information.

ELECTRICAL

MAIN OFFICE

- Provide one dedicated duplex outlet for the main computer, installed at standard height, within 3' of final placement of computer.
 - Coordinate with data requirements.
- Provide one dedicated duplex outlet for the electronic door strike and access control system within 3' of the final placement of the DVR, security panel, sound amplifier/receiver, and CCTV power supply.
 - If the security panel and/or CCTV power supply are installed above the ceiling, provide an additional 110V duplex outlet.
 - Verify that this is allowed by your local electric code.
 - Coordinate with security requirements.
- Provide additional outlets near phone jacks for use with electronics.
 - Coordinate with data requirements.
 - No exposed conduit allowed.

TRAINER'S OFFICE

- Provide a minimum of two 110V outlets or what is required per electrical code (whichever is greater).

TANNING ROOM(S) (if applicable)

- Provide one dedicated outlet for the tanning bed.
 - Verify specific voltage, amperage, and outlet type with tanning bed vendor.
- Provide additional outlets for a fan and/or a radio, if desired.

HYDRO MASSAGE ROOM(S) (if applicable)

- Provide one dedicated outlet for the Hydro Massage.
 - Verify specific voltage, amperage, and outlet type with Hydro Massage vendor.
- External cooling system may be required, depending on your room size and available HVAC requirements. If needed, external cooling system must be placed out of site of the Hydro Massage.

TOILET/SHOWER ROOM

- Provide one GFCI 110V outlet above sink, next to the mirror for razors, hair dryers, etc.

UTILITY ROOM

- Provide a minimum of one 110V outlet or what is required per electrical code (whichever is greater).

CABLE TELEVISION & INTERNET

General

- Cable outlets to be installed as required for cardio equipment and wall-mounted TV locations.
- Internet connections to be installed as required at offices and security system locations.

ELECTRICAL

Cardio

- **Single Row of Cardio**

- Use a surface mounted raceway – Legrand AL5200 Raceway
- Located along the storefront mullion
- Brushed Aluminum

- **Second Row of Cardio**


- Power to be feed inside wall, down to the floor.
- Surface mounted conduit on the wall is **NOT** allowed.
 - In-Floor Electrical Box– Walker RFB4-CI-1 Floor box
- OR
- Surface mounted raceway – Legrand ALDS4000 Series Raceway
 - Lower profile, radius edge
 - Brushed Aluminum
 - Provides clean, slim look
 - Need to minimize possible trip hazards
- Knee walls are **NOT** allowed, they provide unwanted barriers in the club



Surface Mounted Raceway – Single Row



In-floor Electrical Box – Second Row



Surface Mounted Raceway – Second Row

PLUMBING

TOILET/SHOWER ROOM(S)

- Provide a drain in all showers.
 - Slope shower floor/pan from shower walls and entrance lip to drain location.
 - If the shower has no entrance lip (due to ADA requirements), slope from edge of shower floor/pan.
- Provide an additional drain in the toilet/shower room floor to prevent flooding of the toilet room floor.

UTILITY ROOM

Average water consumption for a 4,000 sq.ft. club is 350 gallons per-day, or 10,500 gallons a month, depending on quantity of showers. Recommended options for water heaters (based on average water usage) is as follows:

1. Install a tank-style water heater, 50 gallons, recommended for two toilet rooms with a shower.
2. Install a 80 gallons size for three or more toilet rooms with showers.
 - For higher usage, adjust accordingly.

OR

3. Install one tankless, on-demand water heater providing up to 4.5 gallons per-minute (GPM) for one toilet room with a shower.
 - For two or more toilet rooms with showers, increase GPM to 5.3 (or higher).
4. Install two tankless, on-demand water heaters if you anticipate a high percentage of members that will use the showers.

AND

5. Provide and install one mop sink.

DRINKING FOUNTAIN

- Provide as-shown on Compliance Drawing (or as required by code).
- At least one drinking fountain is required. Refer to compliance drawing for location. Additional drinking fountains may be required by the governing authorities. Verify with your local design professional and local governing jurisdiction.
- Drinking fountains with the bottle filler feature is recommended.
- Order thru the vendor portal.

Preferred Vendor: Elkay Manufacturing Company
Customer Service: 651-982-9802
bob@bongard.com



INFORMATION TECHNOLOGY

PHONES

The following phone lines are **REQUIRED** for your club. Additional lines may be added in the office(s), if desired.

- Line 1 for your main office phone.
- Line 2 for your fax and credit card terminal (DSL if applicable).
- Line 3 (analog) for your 911 emergency phone (configured for local calls only).
 - Your emergency phone line must be installed in plain view of the workout areas.
 - Mount the jack at 46" AFF and provide a wall-mounted phone and "911 Call Access" sign directly above the phone.

DATA/INTERNET ACCESS

- Broadband access (DSL, cable, etc.) with a static IP address is REQUIRED for your club. The static IP address (one that does not change) is required for remote computer support and remote viewing of the CCTV system through the DVR.
- Most Internet Service Providers (ISP) that provide broadband access also provide a modem with their service.
- Ask your ISP for the user name and password to access the router, as we will need to port forward to the DVR & security for remote access.
- A router or switch is required. We recommend that the Security provider include this switch in their equipment quote to eliminate compatibility issues and maximize remote support.
- A router allows multiple PCs, and other devices, such as the DVR & security, to access the internet simultaneously. It also provides a firewall to protect the local network from malicious attacks. We recommend that the Security provider include this router in their equipment quote to eliminate compatibility issues and maximize remote support.
- Order your internet service at least 60 days prior to your tentative opening date.

CABLE

- Programming source (cable, satellite, etc.) is necessary for TVs and LCD screens (on cardio equipment) in the cardio area.
 - **NO EXPOSED CABLES ALLOWED for TV's and LCD Screens**

Main Office:

- Install phone jacks for required phone lines 1 & 2, and additional jacks for computer(s), as-necessary.
 - Coordinate with Security and Electrical (based on computer location(s)).
- Provide Broadband for high-speed Internet access.
 - Coordinate with Security and Electrical (based on computer location(s)).

INFORMATION TECHNOLOGY

CABLE (continued)

Trainer's Office:

- Install one phone jack (on main phone line or additional phone line if provided).
- Provide broadband for high-speed internet access, if desired.
 - Coordinate with electrical (based on computer location).

Cardio Area:

- Provide cable connections to all TVs.
- Provide cable connections to all equipment mounted LCD screens.

Preferred Vendor: Broadcast Vision Entertainment

Customer Service: 888-330-4283 x 1

sales@broadcastvision.com

Preferred Vendor: Direct TV – National Accounts

Customer Service: 866-949-4504

nationalaccounts@directtv.com

TV's

- Typically size range is 50" to 55".
- Brand is not important.
- Buy base model
- No need for HD, unless paying for HD service with your provider.

TV CEILING MOUNT

- Install unistrut's for support where the trusses are made out of metal.
- Typically attach at the bottom of the metal truss and span across two trusses, with the opening facing the floor.
- Specifications: 1 5/8" x 1 5/8", 12 gauge, with a minimum of two points of contact required.
- Verify manufacture, landlord and local code requirements prior to installation.
- Supplied by the Owner or General Contractor.

TV WALL MOUNT

- Install an external support to span between metal or wood studs.
- Designed for use on 25 gauge or heavier metal studs to safely span the load between two studs (applies to 16", 20", or 24" centers).
- Verify gauge and spacing of existing or new studs with contractor.
 - Typical commercial buildings use heavier gauge studs for the perimeter (outside) walls and thinner gauge for internal walls.

SECURITY

Before ProVision Security Solutions (PSS) can begin the installation process, certain aspects of your build-out must be complete. The following information outlines these requirements. Please review these with your contractor and/or other vendors. For detailed questions about the additional requirements, please contact ProVision at 866.315.0777.

DOOR LOCK

For this component, you should contact a local, and trusted, locksmith. Your builder may have a preferred vendor for this type of work. It's best to contact the locksmith early in the build-out; doing so will allow any special order items to arrive on time. The recommended door latch is a normally secure electronic door strike. PSS strongly encourages the installation of the electronic door strike, rather than a magnetic lock. Your member entrance will control member access while allowing free exiting of members. Typically your existing doors will work, however they may need to be retro-fitted with an electronic release mechanism. It is also required that your member door(s) swing outward. If your door does not currently swing outward, adjustments will need to be made prior to the security installation. There are many different types of entrances so the best way to determine what your particular entrance will require is to meet with a local locksmith. A ProVision installer will connect the access control wiring to the electronic device the locksmith will install. The information below will help your locksmith understand the requirements for this installation.

DOOR LOCK REQUIREMENTS

Before a Technician can arrive at the club, you must provide your Provision Project Manager with adequate pictures show the door lock complete.

The three main scenarios we see in Anytime Fitness gyms and their typical solutions are as follows:

Door Type	Recommended Door Lock System
Single Door	Electric Strike
Double Door With permanent mullion	Electric Strike
Double Door without permanent mullion (doors close together with no center rail)	Removable Mullion System

Electric Strike: An electronic strike will be cut into the door frame, a free exiting device with a spring latch is installed (i.e. crash bar or crash paddle), and a latch guard is installed on the exterior of the door to prevent tampering with the strike and latch. Anytime Fitness recommends the installation of a door latch guard to protect a strike from being damaged from the outside.

Locksmith requirements for electric strike:

- The strike will need to operate off 12 VDC.
- The locksmith will need to provide a 12 VDC rated lock power supply or plug-in transformer.
- Provide and install armored loop, if needed.
- Install the control cable from the strike to the duplex outlet above the door and test lock.

SECURITY

REMOVABLE MULLION SYSTEM

The removable mullion is installed (center rail installed from floor to top rail of the door frame on the interior of the space, the doors close up to the rail, this rail does not physically go between the doors), doors are fitted with crash bars that close to the center mullion, and an armored loop or power transfer hinge is installed to allow control wire to transfer from door to frame. A latch guard will not be necessary in this scenario as all locking components are internal and protected from tampering.

Locksmith requirements for removable mullion:

- Operates at 12 VDC.
- The locksmith will need to provide a 12 VDC plug-in transformer.
- Fail secure.
- Free exiting devices: one powered crash bar & one standard crash bar with dogging .
- Provide and install armored loop, if needed.
- Control wire run from powered crash bar through power transfer hinge or armored loop with enough wire to reach the outlet above the door.
- TEST SYSTEM.

MAG LOCK

It is not recommended by PSS, but if a magnetic lock is required, then an override key needs to be installed on the exterior of the door. This allows entry to the club when the access control program is not available or provides an additional keyed entrance, if necessary.

Locksmith Requirements for Mag Lock:

- Operates at 12 or 24 volts DC.
- Minimum of 6 hours of battery backup.
- key override on the exterior of the door, 12 or 24 volts DC.
- 2 free exit devices (RTE button is required).

ELECTRICAL OUTLETS - Requirements:

- Permanent power is required PRIOR to installation One double duplex 110V outlet above each member entrance door.
- This outlet will be used by the electronic door strike and the access control system
- One double duplex 110V outlet behind each tanning bed.
 - Please confirm with your tanning bed and massage manufacturer, if applicable, the outlet specifications required to operate your tanning beds.
- One double duplex outlet in the office, near the computer desk.
 - The outlet must be within 3 feet of the final placement of the desk that will hold the club's main computer, and it should be installed at standard outlet height.
- Dedicated 15 amp circuit with double duplex outlet installed within 5' of the rack system at standard outlet height.
- One double duplex 110V outlet near final placement of the security panel (behind rack system).
- We also recommend additional outlets in the office for printers, lamps, and other accessories.

SECURITY

LOW VOLTAGE WIRING

It is best practice to locate your modem and router/switch together in the rack system. If the modem and router/switch are not located together, your contractor will be responsible for running one CAT5e cable from the modem to the location of router/switch

If your managed router is located in the rack system, ProVision Security will run individual CAT5e cables from the managed router/switch to items located in the rack system (DVR/NVR, AccessPro and security panel). If your managed router is not located in the rack system, your electrician or contractor will be responsible for the individual CAT5e runs from the router to the rack components. Additionally, your electrician or contractor is responsible for any long CAT5e runs to any other device that you have that requires internet (i.e. Wellbeats or Wexer kiosk, computer in a different room than rack system). ProVision Security does not do any TV wiring.

INTERNET

Internet access **MUST** be ordered and installed prior to our technician arriving onsite. You are required to send pictures of the modem powered on and set up to your ProVision Project Manager, prior to the Technician Arriving at the club. Anytime Fitness Corporate requires that you have functional remote viewing of your cameras. A static IP address must be purchased from your Internet Service Provider for you to view the DVR remotely.

PHONE

The security system will be integrated with an alarm monitoring service. ProVision Security will use a cellular network to for your security panel to communicate and transmit signals to the central monitoring station. This cellular network connectivity eliminates the need to connect a phone line to your security panel for communication.

You will need to purchase a dedicated phone line for your 911 emergency phone. This line is always available for an emergency call, and is typically located near your AED and hardwired panic button. Please note: This line can be any of the types listed above.

SECURITY SYSTEM

The security panel will be located on the wall behind rack. A motion detector must be installed in the room the rack system is located in, protecting the security panel from tampering. The power source for the security panel will be supplied by a 15 amp dedicated circuit (see "Electrical Outlets" (above) for details.)

Please keep extra batteries on-hand for replacement for wireless door contacts and panic devices.

Some local municipalities require a permit to operate a security system. Check with your local authorities to see if this is the case in your area.

In-addition to the security system components, the following items must be installed on the premises:

1. A telephone for 911 call access.
2. A sign in plain view with an advisory warning that indicates members of a non-staffed health spa should be aware that working-out alone may pose risks to their health and safety.

SECURITY

EQUIPMENT INSTALLATION AND GENERAL CONSTRUCTION REQUIREMENTS

ProVision Security will assign you to a dedicated Project Manager that will walk you through from sales and design, to the implementation and opening of your club. Please be sure to be reaching out to Provision 12 weeks in advance, so proper planning can take place.

Before your security system installed, certain aspects of your build-out must be completed by your General Contractor. Your ProVision Project Manager will provide you with an *Additional Requirements Checklist* two weeks prior to your tentative installation date to confirm those items have been completed, you may also asked to send photos as supporting documents.

ALARM PERMITS

Contact your local authorities for information regarding alarm permits. Occasionally emergency professionals require businesses to apply for an alarm permit. If an alarm permit is mandated by your local municipality, you will be required to apply for and purchase this permit for the operation of your alarm system. Please view the False Alarm Policy on the [Security Monitoring and Testing](#) Page of the Anytime Fitness Academy.

Mandatory Vendor: ProVision Security
Customer Service: 1-866-315-0777
helpdesk@provisionsecurity.com

SOUND

MUSIC LICENSING AND MESSAGING SYSTEMS

A quality sound system that plays upbeat music will improve the workout experience for your members. Keep in-mind, however, that you must obtain permission from the owner of the music or their representative before you can legally play it in your club. This may sound complicated, but when you partner with a music service, they will provide you with licensed music. A music system can also be integrated with a messaging component.

Preferred Vendor: Mood Media (Pandora Provider)
Customer Service: 1-800-345-5000
anytimefitness@moodmedia.com

Preferred Vendor: Rockbot
Customer Service: 415-813-6020 x 23
chris@rockbot.com

Preferred Vendor: Vibenomics
Customer Service: 317-455-6947
ozelle.h@vibenomics.com



SIGNAGE

Signage

EXTERIOR SIGNS

Your exterior signage may be the first encounter your market has with Anytime Fitness. Therefore, you need to give this component of your business the attention it deserves! To ensure a strong brand identity, your Anytime Fitness sign and Running Man logo must be built per the Anytime Fitness standards.

To help you achieve this goal, we have worked with a select group of vendors to optimize our signage specifications. The result is a greatly improved design that displays the true Anytime Fitness purple! This was made possible by partnering with industry leaders to develop a custom purple vinyl. The custom purple vinyl is **REQUIRED** for all exterior signage and is only available through the Designated Sign Vendors. The Designated Sign Vendors will work with you to achieve a look that is consistent with our brand image and complements your building site. There are many benefits to the program including; the custom purple vinyl, a complete warranty, automatic approval from corporate, reduced pricing and cradle to grave service. From design through installation and beyond the Designated Vendors are committed to you.

A couple of additional items to consider with your exterior signage. It is strongly recommended to include your exterior signage shop drawings in your lease, it is a great time for the Landlord to approve and can prevent problems later during the buildout. Check with your real estate broker for details. As a Franchisee, you assume all accountability for the signage, including approvals and inspection by all required parties.

The final power hook up and optional timer may have to be completed by a licensed electrician, confirm with your local building codes. In this case most sign installers are not able to make this final connection. You will need to coordinate this task with your general contractor. Be aware this may incur an extra cost.

Designated Vendor Responsibilities:

- Conduct a site survey of your space.
- Review local codes regarding exterior signage.
- Review Landlord sign criteria per your final lease.
- Provide you with a shop drawing showing the proposed signage per the Anytime Fitness sign specifications, Landlord sign criteria and local codes.
- Obtain Landlord approval.
- Obtain required city permits and inspections.
- Arrange installation of exterior signage.
- Provide applicable warranty for signage.

EXTERIOR SIGNS (continued)

When working with one of our designated vendors, you do not need to supply shop drawings to your Franchise Business Consultant, the designated vendor will take care of all the required pre-approvals, Landlord approvals, permits and installation.

Designated Vendor: Archetype – Jenny Kruse

Manufactured in Minnesota

Customer Service: 888-512-1272 x9602

customerservice@archetypesign.com

Designated Vendor: nPrint Graphix – Todd Yearack

Manufactured in Missouri

Customer Service: 888-518-7344

417-882-7446

todd@nprintgraphix.com

Designated Vendor: Tube Art Group (TAG) – Paul Genge

Manufactured in Washington State & Georgia

Customer Service: 253-709-8310

509-469-8186 x1403

anytimefitness@tubeart.com

pgenge@tubeart.com

INTERIOR SIGNAGE & GRAPHICS

A comprehensive interior signage and graphics program has been developed for your club. Refer to the Anytime Fitness Signage Style Guide and Order Guide on the dashboard for the Designated vendor, specifications & requirements.

Designated Vendor: Archetype – Jenny Kruse

Customer Service: 888-512-1272 x9602

customerservice@archetypesign.com





APPENDIX



- FOR STONE OPTION NOTE
- NUMBER OF CORNERS
- HATCH AREA INDICATES WALL COVERING OR STONE VENEER
- WIDTH IS 8'-0" WITH SHELVING
- CENTERED U.N.O.
- HEIGHT IS 10'-0" A.F.F. U.N.O. - SEE ELEVATIONS




FREESTANDING

EX 1A

3/8" = 1'-0"

2 CORNERS




PERPENDICULAR

EX 1B

3/8" = 1'-0"

1 CORNER




OVERHANG

EX 1C

3/8" = 1'-0"

3 CORNERS



OVERHANG WITH TWO WAY MIRROR


EX 1D

3/8" = 1'-0"

3 CORNERS




NOTE:
SHELVING UNIT
TO BE
MANUFACTURED
BY PREFERRED
MILLWORK
VENDOR - SEE
DASHBOARD
FOR ORDERING
INFORMATION




FREESTANDING WALL PLAN

2 1A 3/8" = 1'-0"




FREESTANDING WALL ELEVATION

3 1A 3/8" = 1'-0"



FREE STANDING WALL SECTION


1 1A 3/8" = 1'-0"



PERPENDICULAR WALL PLAN

3/8" = 1'-0"

EXISTING ROOF ASSEMBLY - VARIES



PERPENDICULAR WALL ELEVATION

3/8" = 1'-0"

FREE STANDING WALL SECTION

3/8" = 1'-0"

NOTE: SHELVING UNIT TO BE MANUFACTURED BY PREFERRED MILLWORK VENDOR - SEE DASHBOARD FOR ORDERING INFORMATION



LOGO WALL

PERPENDICULAR


March 2017

WILKUS ARCHITECTS

10 North Avenue North, Naperville, IL 60563
Phone: 630.241.1000 www.wilkusarch.com


EXHIBIT

1B



OVERHANG WALL PLAN


2
1C
3/8" = 1'-0"



OVERHANG WALL ELEVATION

3
1C
3/8" = 1'-0"

NOTE:
SHELVING UNIT TO BE
MANUFACTURED BY
PREFERRED MILLWORK
VENDOR - SEE
DASHBOARD FOR
ORDERING INFORMATION




OVERHANG WALL SECTION

1
1C
3/8" = 1'-0"



NOTE:
SHELVING UNIT TO BE MANUFACTURED BY PREFERRED MILLWORK VENDOR - SEE DASHBOARD FOR ORDERING INFORMATION




OVERHANG TWO WAY MIRROR WALL

3/8" = 1'-0"

PLAN

TERMINATE FINISH AT CEILING UP TO 11'-0" OR 10'-0" A.F.F. WITH OPEN CEILING



OVERHANG TWO WAY MIRROR WALL


3/8" = 1'-0"

ELEVATION

OVERHANG TWO WAY MIRROR WALL


3/8" = 1'-0"

SECTION



LOGO WALL CASE DETAIL

3
1H
1" = 1'-0"




TOP OF STONE DETAIL

4
1H
3" = 1'-0"

VINYL COVERING WALL TYPE 5/8" TYPE 'X' GYPSUM BOARD 3-5/8" METAL STUDS @ 16" O.C. AIR SPACE 6" METAL STUDS @ 16" O.C. 5/8" GYPSUM BOARD VINYL WALL COVERING	STONE WALL TYPE 5/8" TYPE 'X' GYPSUM BOARD 3-5/8" METAL STUDS @ 16" O.C. AIR SPACE 6" METAL STUDS @ 16" O.C. 5/8" CEMENTITIOUS SHEATHING CULTURED VENEER STONE
--	---


WALL TYPES

5
1H
1/4" = 1'-0"




LOGO WALL END DETAIL

1
1H
1" = 1'-0"



OVERHANG END DETAIL

2
1H
1" = 1'-0"




3 TWO WAY MIRROR CASE DETAIL

1" = 1'-0"


1 TWO WAY MIRROR CASE DETAIL

1" = 1'-0"



2 COLUMN BASE PLATE DETAIL


1 1/2" = 1'-0"



NOTE: UNIT TO BE MANUFACTURED BY PREFERRED MILLWORK FABRICATOR - SEE DASHBOARD FOR ORDERING INFORMATION


1
1H.2
1" = 1'-0"

**TWO WAY MIRROR SHELVING CASE
DETAIL**



2
1H.2
1" = 1'-0"


TWO WAY MIRROR PLAN SECTION



3
1H.2
1" = 1'-0"


TWO WAY MIRROR SECTION

NOTE: UNIT TO BE
MANUFACTURED BY
PREFERRED MILLWORK
FABRICATOR - SEE
DASHBOARD FOR
ORDERING
INFORMATION




STANDARD CASE DETAIL

1
1H.3
1" = 1'-0"




STANDARD CASE PLAN SECTION

3
1H.3
1" = 1'-0"



STANDARD CASE SECTION


2
1H.3
1" = 1'-0"



FREESTANDING INSPIRATION WALL

EX 2A


3/8" = 1'-0"



PERPENDICULAR INSPIRATION WALL

EX 2B


3/8" = 1'-0"



ATTACHED INSPIRATION WALL

EX 2C


3/8" = 1'-0"




OVERHANG INSPIRATION WALL

EX 2D

3/8" = 1'-0"







1 2A 3/8" = 1'-0"

FREESTANDING INSPIRATION WALL


PLAN



SEE COMPLIANCE
DRAWING FOR
PAINT COLORS




SEE COMPLIANCE
DRAWING FOR
PAINT COLORS




PERPENDICULAR INSPIRATION WALL PLAN

2 2B 3/8" = 1'-0"





PERPENDICULAR INSPIRATION WALL ELEVATION

3 2B 3/8" = 1'-0"



PERPENDICULAR INSPIRATION WALL SECTION

1 2B 3/8" = 1'-0"




2
2C

1
2C

ATTACHED INSPIRATION WALL

3/8" = 1'-0"

PLAN



3
2C


ATTACHED INSPIRATION WALL

3/8" = 1'-0"

ELEVATION

SEE COMPLIANCE
DRAWING FOR PAINT
COLORS

INSTALLATION: ASSEMBLE 2X6 FRAMING PER DETAIL 3/2C AND ANCHOR TO EXISTING WALL. INSTALL AND FINISH GYPSUM BOARD AROUND 2X6 PERIMETER AND PAINT BLACK. INSTALL 2X4'S, SUBSTRATE AND GYPSUM BOARD, FINISH AND PAINT REMAINING EXPOSED GYPSUM BOARD TO MATCH ADJACENT WALL.





1
2C

ATTACHED INSPIRATION WALL


3/8" = 1'-0"

SECTION



SEE COMPLIANCE
DRAWING FOR PAINT
COLORS




2 OVERHANG INSPIRATION WALL
3/8" = 1'-0"



3 OVERHANG INSPIRATION WALL
3/8" = 1'-0"




1 OVERHANG INSPIRATION WALL
3/8" = 1'-0"



COLUMN BASE PLATE DETAIL

1
2D
3" = 1'-0"



INSPIRATION WALL DETAIL


2
2D
1 1/2" = 1'-0"



FREE STANDING MANIFESTO WALL

EX
3A


3/8" = 1'-0"



CEILING RETURN MANIFESTO WALL PLAN

EX
3B


3/8" = 1'-0"



ATTACHED MANIFESTO WALL PLAN

EX
3C

3/8" = 1'-0"



PERPENDICULAR MANIFESTO WALL PLAN



EX
3D

3/8" = 1'-0"







SEE COMPLIANCE DRAWING FOR PAINT COLORS





3 3A **FREESTANDING MANIFESTO WALL** **PLAN** **3/8" = 1'-0"**



1 3A **FREESTANDING MANIFESTO WALL** **ELEVATION** **3/8" = 1'-0"**


2 3A **FREESTANDING MANIFESTO WALL** **SECTION** **3/8" = 1'-0"**





PERPENDICULAR MANIFESTO WALL PLAN


2
3D
3/8" = 1'-0"



PERPENDICULAR MANIFESTO WALL ELEVATION



3
3D
3/8" = 1'-0"

SEE COMPLIANCE
DRAWING FOR
PAINT COLORS




PERPENDICULAR MANIFESTO WALL SECTION

1
3D
3/8" = 1'-0"




OVERHANG MANIFESTO WALL
PLAN
2 3/8" = 1'-0"




OVERHANG MANIFESTO WALL
ELEVATION
3 3/8" = 1'-0"

SEE COMPLIANCE
DRAWING FOR
PAINT COLORS




OVERHANG MANIFESTO WALL
SECTION
1 3/8" = 1'-0"



COLUMN BASE PLATE DETAIL


1
3H 3" = 1'-0"



ATTACHED GRAPHIC WALL DETAIL

2
3H 1 1/2" = 1'-0"

BLOCKING LOCATION REFERENCE



ITEMS REQUIRING BLOCKING

- TELEVISIONS
- SHOWER SEATS
- GRAB BARS
- LAVATORIES
- WALL MOUNTED SHELVING
- RESTROOM/TANNING MIRRORS
- FITNESS ON REQUEST KIOSK

NOTE:

• FOR TRX/TORQUE WALL MOUNTED EQUIPMENT, CONTRACTOR MUST BUILD A REINFORCED WALL WITH ADDITIONAL BLOCKING - REFER TO MANUFACTURER SPECIFICATIONS.


• BLOCKING HEIGHT LOCATIONS WILL VARY DUE TO INSTALLATION HEIGHTS AND CODE REQUIREMENTS - VERIFY PRIOR TO INSTALLING.



BLOCKING DETAILS




15 North Avenue North, Hopkins, MN 55343
Phone: 952.341.8888 www.wilkusarch.com




1
BLKG-2 1 1/2" = 1'-0"

PLYWOOD BLOCKING




2
BLKG-2 1 1/2" = 1'-0"

2x WOOD BLOCKING




3
BLKG-2 1 1/2" = 1'-0"

PLYWOOD BLOCKING




4
BLKG-2 1 1/2" = 1'-0"

2x WOOD BLOCKING



LOW STEP WALL CAP DETAIL

3 LW 3" = 1'-0"



LOW STEP WALL ELEVATION

1 LW 1/4" = 1'-0"

INSTALL WALL BASE TRACK & ANCHOR TO FLOOR - INSTALL COLUMN & BASE PLATE ON TOP OF BASE TRACK - ANCHOR STUDS TO EACH SIDE OF COLUMN TO ENSURE STUDS ARE ANCHORED TO TOP & BOTTOM TRACKS

1/2" x 4-1/2" HILTI HY 200 ADHESIVE ANCHORING SYSTEM - 4 BOLTS EACH SIDE OF COLUMN - TYPICAL

CENTERLINE OF STEEL COLUMN TO BE 9" MAXIMUM FROM OUTSIDE EDGE OF FINISHED WALL ASSEMBLY - VERIFY DIMENSION ALLOWS BASE PLATE TO BE COMPLETELY CONCEALED WITHIN WALL ASSEMBLY


STEEL COLUMN ASSEMBLY TO BE USED WHEN STEP WALL ABUTS AN EXISTING WALL THAT CANNOT BE MODIFIED TO INCLUDE PLYWOOD BACKING AS SHOWN BELOW

INSTALL WALL BASE TRACK & ANCHOR TO FLOOR - INSTALL COLUMN & BASE PLATE ON TOP OF BASE TRACK - ANCHOR STUDS TO EACH SIDE OF COLUMN TO ENSURE STUDS ARE ANCHORED TO TOP & BOTTOM TRACKS

INSTALL 6" STEEL STUD CENTERED ON STEEL COLUMN EACH SIDE - ATTACH AS REQUIRED

3-1/2" SQUARE 3/8" STEEL TUBE COLUMN - WELD TO BASE

3/8" X 3-1/2" X 12" BASE PLATE



LOW STEP WALL SECTION

2 LW 1 1/2" = 1'-0"

INSTALL WALL BASE TRACK & ANCHOR TO FLOOR - INSTALL COLUMN & BASE PLATE ON TOP OF BASE TRACK - ANCHOR STUDS TO EACH SIDE OF COLUMN TO ENSURE STUDS ARE ANCHORED TO TOP & BOTTOM TRACKS

1/2" x 4-1/2" HILTI HY 200 ADHESIVE ANCHORING SYSTEM - 4 BOLTS EACH SIDE OF COLUMN - TYPICAL

CENTERLINE OF STEEL COLUMN TO BE 9" MAXIMUM FROM OUTSIDE EDGE OF FINISHED WALL ASSEMBLY - VERIFY DIMENSION ALLOWS BASE PLATE TO BE COMPLETELY CONCEALED WITHIN WALL ASSEMBLY


STEEL COLUMN ASSEMBLY TO BE USED WHEN STEP WALL ABUTS AN EXISTING WALL THAT CANNOT BE MODIFIED TO INCLUDE PLYWOOD BACKING AS SHOWN BELOW

INSTALL WALL BASE TRACK & ANCHOR TO FLOOR - INSTALL COLUMN & BASE PLATE ON TOP OF BASE TRACK - ANCHOR STUDS TO EACH SIDE OF COLUMN TO ENSURE STUDS ARE ANCHORED TO TOP & BOTTOM TRACKS

INSTALL 6" STEEL STUD CENTERED ON STEEL COLUMN EACH SIDE - ATTACH AS REQUIRED


3-1/2" SQUARE 3/8" STEEL TUBE COLUMN - WELD TO BASE

3/8" X 3-1/2" X 12" BASE PLATE



LOW STEP WALL SECTION


4 LW 1 1/2" = 1'-0"



1
CTB-1

COLOR TRANSITION BUMP OUT ELEVATION

1/2" = 1'-0"



2
CTB-1

COLOR TRANSITION BUMP OUT DETAIL

3" = 1'-0"




WILKUS
ARCHITECTS

15 Ninth Avenue North
Hopkins, MN 55343
Phone: 952.941.8660
www.wilkusarch.com



CTB-1



DOOR

DOOR SWING
DOORS SHALL BE PERMITTED TO SWING INTO THE REQUIRED TURNING SPACE. IF RESTROOM IS FOR INDIVIDUAL USE AND CLEAR FLOOR SPACE IS PROVIDED WITHIN THE ROOM BEYOND THE ARCH OF THE DOOR SWING, THEN THE DOOR MAY SWING INTO THE CLEAR FLOOR SPACE OF RESTROOM FIXTURES.

CLEARANCE

D - PUSH FRONT APPROACH DOOR WITH BOTH LATCH AND CLOSER SHALL HAVE CLEAR FLOOR SPACE 48 INCHES MINIMUM PERPENDICULAR TO DOORWAY AND 12 INCHES PARALLEL BEYOND THE LATCH SIDE OF THE DOOR.
E - PULL FRONT APPROACH DOOR WITH BOTH LATCH AND CLOSER SHALL HAVE CLEAR FLOOR SPACE 60 INCHES MINIMUM PERPENDICULAR TO DOORWAY AND 18 INCHES PARALLEL BEYOND THE LATCH SIDE OF THE DOOR.

TOILET

THE CENTERLINE OF THE TOILET SHALL BE 16 INCHES MINIMUM TO 18 INCHES MAXIMUM FROM THE SIDE WALL.

CLEARANCE

A - THE REQUIRED CLEARANCE SPACE AROUND THE TOILET 60 INCHES MINIMUM MEASURED PERPENDICULAR FROM THE SIDE WALL TO 56 INCHES MAXIMUM MEASURED PERPENDICULAR FROM THE REAR WALL. SINK MAY NOT BE IN THIS SPACE.
THE SEAT HEIGHT OF THE TOILET ABOVE THE FINISH FLOOR SHALL BE 17 INCHES MINIMUM AND 19 INCHES MAXIMUM MEASURED FROM THE TOP OF THE SEAT.

GRAB BARS

GRAB BARS
GRAB BARS SHALL BE PROVIDED ON THE SIDE WALL CLOSEST TO THE WATER CLOSET, ON THE REAR WALL, AND ON THE CONTROL AND BACK WALL OF THE SHOWER.

SIDE WALL

THE SIDE WALL GRAB BAR SHALL BE 42 INCHES LONG MINIMUM, LOCATED 12 INCHES MAXIMUM FROM THE REAR WALL AND EXTENDING 54 INCHES MINIMUM FROM THE REAR WALL.

REAR WALL

THE REAR WALL GRAB BAR SHALL BE 36 INCHES LONG MINIMUM AND EXTEND FROM THE CENTERLINE OF THE TOILET 12 INCHES MINIMUM ON ONE SIDE AND 24 INCHES MINIMUM ON THE OTHER SIDE.

VERTICAL

VERTICAL GRAB BAR 18 INCHES MINIMUM IN LENGTH SHALL BE MOUNTED WITH THE BOTTOM OF THE BAR LOCATED 38 INCHES MINIMUM AND 41 INCHES MAXIMUM ABOVE THE FLOOR, AND WITH THE CENTERLINE OF THE BAR LOCATED 38 INCHES MINIMUM AND 41 INCHES MAXIMUM FROM THE REAR WALL.

SHOWER HORIZONTAL GRAB BAR

HORIZONTAL GRAB BARS SHALL BE PROVIDED ACROSS THE CONTROL WALL AND ON THE BACK WALL TO A POINT 18 INCHES FROM THE CONTROL WALL.

SHOWER VERTICAL GRAB BAR

VERTICAL GRAB BARS 18 INCHES MINIMUM IN LENGTH SHALL BE PROVIDED ON THE CONTROL END WALL 3 INCHES MINIMUM AND 8 INCHES MAXIMUM ABOVE THE HORIZONTAL GRAB BAR, AND 4 INCHES MAXIMUM INWARD FROM THE FRONT EDGE OF THE SHOWER.

SINK

CLEARANCE
C - THE CLEAR FLOOR SPACE SHALL BE 30 INCHES WIDE MINIMUM BY 48 INCHES DEEP MINIMUM FOR FORWARD APPROACH.

HEIGHT

THE FRONT OF LAVATORIES AND SINKS SHALL BE 34 INCHES MAXIMUM ABOVE THE FLOOR, MEASURED TO THE HIGHER OF THE RIM OR COUNTER SURFACE.

SHOWER

SIZE
TRANSFER-TYPE SHOWER COMPARTMENT SHALL HAVE A CLEAR INSIDE DIMENSION OF 36 INCHES IN WIDTH AND 36 INCHES IN DEPTH, MEASURED AT CENTER POINT OF OPPOSING SIDES. AN ENTRY 36 INCHES MINIMUM IN WIDTH SHALL BE PROVIDED.

CLEARANCE


G - A CLEARANCE OF 48 INCHES MINIMUM IN LENGTH MEASURED PERPENDICULAR FROM THE CONTROL WALL, AND 36 INCHES MINIMUM IN DEPTH SHALL BE PROVIDED ADJACENT TO THE OPEN FACE OF THE COMPARTMENT.

CONTROLS


THE CONTROLS, FAUCETS AND SHOWER SPRAY UNIT SHALL BE INSTALLED ON THE SIDE WALL OPPOSITE THE SEAT 38 INCHES MINIMUM AND 48 INCHES MAXIMUM ABOVE THE SHOWER FLOOR AND SHALL BE LOCATED ON THE CONTROL WALL 15 INCHES MAXIMUM FROM THE CENTERLINE OF THE SEAT TOWARD THE SHOWER OPENING.

L-SHAPED SEATS

A FOLDING OR NON-FOLDING SEAT SHALL BE PROVIDED ON THE WALL OPPOSITE TO THE CONTROL WALL. THE HEIGHT OF SHOWER COMPARTMENT SEAT SHALL BE 17 INCHES MINIMUM AND 19 INCHES MAXIMUM ABOVE THE BATHROOM FLOOR, MEASURED TO THE TOP OF THE SEAT. THE SEAT SHALL BE 36 INCHES MINIMUM AND 48 INCHES MAXIMUM IN WIDTH. THE SEAT SHALL BE 15 INCHES MINIMUM AND 20 INCHES MAXIMUM IN DEPTH. THE REAR EDGE OF THE SEAT SHALL BE 15 INCHES MAXIMUM FROM THE REAR WALL AND THE FRONT EDGE SHALL BE 14 INCHES MINIMUM AND 15 INCHES MAXIMUM FROM THE WALL. THE END OF THE "L" SHALL BE 22 INCHES MINIMUM AND 23 INCHES MAXIMUM FROM THE MAIN SEAT WALL.




REFER TO ENLARGED
RESTROOM WITH SHOWER
PLAN FOR NOTES



1
RR-3

ARCHITECTURAL FLOOR PLAN

3/8" = 1'-0"



UNISEX RESTROOM ELEVATION

1/4" = 1'-0"




RESTROOM

DETAILS




15 North Avenue North, Hopkins, MN 55343
Phone: 952.341.8882 www.wilkusarch.com

NOTE: REVIEW LOCAL/STATE ACCESSIBILITY REQUIREMENTS - VERIFY PROPOSED DETAIL IS COMPLIANT PRIOR TO INSTALLATION



1 FLOOR TRANSITION @ SHOWER

RR-4 2" = 1'-0"



2 RESTROOM BASE TILE DETAIL


RR-4 2" = 1'-0"



RESTROOM DETAILS



15 North Avenue North, Hopkins, MN 55343
Phone: 952.941.8882 www.wilkusarch.com




1
RR-5

DRAIN DETAIL

3/4" = 1'-0"

THIS DETAIL PRINCIPLE APPLIES THROUGHOUT

ALWAYS START TILE IN CENTER OF ROOM - NEVER HAVE TILE CUT LESS THAN HALF ITS WIDTH IN ROOMS



2
RR-5

TILE FLOOR TRANSITION @ DOOR


3/4" = 1'-0"



RESTROOM DETAILS



15 North Avenue North, Hopkins, MN 55343
Phone: 952.941.8888 / www.wilkusarch.com



SHOWER RESTROOM PLAN

3/8" = 1'-0"



SHOWER RESTROOM

WALL TILE FINISH




15 North Avenue North, Hopkins, MN 55343
Phone: 952.941.8882 www.wilkusarch.com

GENERAL

1. VERIFY THE LOCATION OF ALL ITEMS WITH OWNER PRIOR TO INSTALLATION.
2. VERIFY IF ANY OF THE PROPOSED TOILET ACCESSORIES WILL BE SUPPLIED BY OWNER.
3. REFER TO B1.0 FOR ACCESSIBLE FIXTURE MOUNTING HEIGHTS.
4. REFER TO A5.0 FOR INTERIOR DECOR FINISHES.
5. BULLNOSE TILE TO MATCH WAINSCOT TILE.
6. GENERAL CONTRACTOR TO INSTALL 5/8" CEMENTITIOUS SHEATHING IN LIEU OF MOISTURE RESISTANT GYPSUM BOARD AT ALL WALL TILE LOCATIONS.
7. BLOCKING: REFER TO "GENERAL NOTES" ON SHEET A5.0.
8. ALL RESTROOM AND SHOWER ROOM ACCESSORIES SUPPLIED AND INSTALLED BY GENERAL CONTRACTOR UNLESS OTHERWISE NOTED.
9. NO EXPOSED COPPER IN RESTROOM.
10. DO NOT TILE BEHIND RESTROOM MIRROR

RESTROOM

- | | |
|--|---|
| 1 WATER RESISTANT GYP. BD.
WALL - PAINT | 15 ROBE HOOK |
| 2 COVED CERAMIC TILE BASE -
REFER TO 2/A7.1 | 16 FLOOR TRANSITION AT SHOWER -
REFER TO 1/A7.1 |
| 3 METAL DOOR FRAME - PAINT | 17 5" X 18" STAINLESS STEEL WALL
SHELF - VERIFY FINAL LOCATION
WITH OWNER |
| 4 WOOD DOOR | 18 18" VERTICAL GRAB BAR |
| 5 TWO WALL SHOWER CRAB BAR | 19 RESTROOM FLOOR DRAIN -
REFER TO 9/A7.2 |
| 6 36" GRAB BAR | 20 PROVIDE POSITIVE SLOPE TO
SHOWER FLOOR DRAINS - IF
SLAB IS EXISTING, REMOVE
PORTION OF SLAB AS NEEDED
AND REPOUR TO REQUIRED
SPECIFICATIONS - COORDINATE
SLOPES WITH FLOORING
CONTRACTOR TO ACHIEVE
CLEAN, SMOOTH TRANSITION |
| 7 42" GRAB BAR | |
| 8 TOILET PAPER HOLDER | |
| 9 PROVIDE TRAP PROTECTION | |
| 10 RECESSED HAND DRYER | |
| 11 ACCESSIBLE LAVATORY | |
| 12 SOAP DISPENSER | |
| 13 24" X 36" POLISHED PLATE GLASS
MIRROR IN STAINLESS STEEL
FRAME - INSTALL MIRROR PRIOR
TO WALL TILE | |
| 14 18" TOWEL BAR | |



SHOWER RESTROOM PLAN

3/8" = 1'-0"




SHOWER RESTROOM

ENLARGED RESTROOM WITH
SHOWER PLAN & NOTES




15 North Avenue North, Hopkins, MN 55343
Phone: (612) 341-8882 www.wilkusarch.com

REFER TO NOTES AND
LAYOUTS ON ENLARGED
RESTROOM WITH SHOWER



UNISEX SHOWER ROOM ELEVATION - RESTROOM 1

3/16" = 1'-0"



UNISEX SHOWER ROOM ELEVATION - RESTROOM 2

3/16" = 1'-0"




SHOWER RESTROOM

ELEVATIONS



15 North Avenue North, Hopkins, MN 55343
Phone: 952.941.8888 www.wilkusarch.com

NOTE:
REFER TO COMPLIANCE
DRAWINGS FOR PAINT COLORS



MATERIAL

WP-1 - NATURAL WOOD PANEL

- MATERIAL -
- PLAIN SLICED WHITE MAPLE VENEER ON 1/4" MDF
- MAPLE WALL CAP 2" X 3/4" WITH 1/4" X 1/2" NOTCH
- EXPOSED ENDS TO BE EDGE BANDED WITH MATCHING VENEER
- TOP COAT - 2 COATS ML CAMPBELL 40 DEGREE SATIN LACQUER
- SEALER ON BACK SIDE - 1 COAT ML CAMPBELL VINYL SEALER

INSTALLATION

- LOCTITE (R) PL PREMIUM(R) POLYURETHANE CONSTRUCTION ADHESIVE
- OPTION TO PIN NAIL THE CORNERS OF THE PANEL AND FILL WITH MATCHING WOOD PUTTY
- INSTALL PANELS WITH 1/16" GAP AND FILL GAP WITH MATCHING SILICONE
- HEIGHT OF PANELS NOT TO EXCEED HEIGHT OF MIRROR




WALL PROTECTION

WAINSCOT OPTION -
48" AND UNDER



15 North Avenue North, Hopkins, MN 55343
Phone: 952.941.8882 / www.wilkusarch.com

NOTE:
REFER TO COMPLIANCE
DRAWINGS FOR PAINT COLORS



MATERIAL

- WP-1 - NATURAL WOOD PANEL
- MATERIAL -
- PLAIN SLICED WHITE MAPLE VENEER ON 1/4" MDF
- MAPLE WALL CAP 2" X 3/4" WITH 1/4" X 1/2" NOTCH
- EXPOSED ENDS TO BE EDGE BANDED WITH MATCHING VENEER
- TOP COAT - 2 COATS ML CAMPBELL 40 DEGREE SATIN LACQUER
- SEALER ON BACK SIDE - 1 COAT ML CAMPBELL VINYL SEALER

INSTALLATION

- LOCTITE (R) PL PREMIUM(R) POLYURETHANE CONSTRUCTION ADHESIVE
- OPTION TO PIN NAIL THE CORNERS OF THE PANEL AND FILL WITH MATCHING WOOD PUTTY
- INSTALL PANELS WITH 1/16" GAP AND FILL GAP WITH MATCHING SILICONE
- HEIGHT OF PANELS NOT TO EXCEED HEIGHT OF MIRROR




WALL PROTECTION


FULL HEIGHT OPTION -
96" AND BELOW




15 North Avenue North, Hopkins, MN 55343
Phone: 952.941.8850 / www.wilkusarch.com



1
WP-3
SECTION
6" = 1'-0"



2
WP-3
ELEVATION
6" = 1'-0"



3
WP-3
PLAN
6" = 1'-0"




WALL PROTECTION

WALL CAP - DETAILS



15 North Avenue North, Hopkins, MN 55343
Phone: 952.341.8882 www.wilkusarch.com

NOTE:
REFER TO COMPLIANCE
DRAWINGS FOR PAINT COLORS



MATERIAL

- 1/16" (.063) THICKNESS - ALUMINUM DIAMOND PLATE - HIGHLY POLISHED

INSTALLATION

- ONLY TO BE INSTALLED UNDER THE MIRRORS AND ABOVE THE BASE
- INSTALL PER MANUFACTURER'S SPECIFICATIONS
- TO BE INSTALLED IN THE FREE WEIGHT AREA
- ONLY TO BE INSTALLED UNDER THE MIRRORS AND ABOVE THE BASE
- DO NOT INSTALL ON THE SIDE OF THE MIRRORS



WALL PROTECTION

DIAMOND PLATE -
UNDER MIRRORS ONLY



15 North Avenue North, Hopkins, MN 55343
Phone: 952.341.8882 www.wilkusarch.com



WALL PROTECTION



Anytime Fitness - Design Manual Revision Tracking

Design Manual	April 2018
Description	Section
General review and updates	All
Updated vendor contacts	All
Updated the ceiling options in the Member Lobby	Pg. 11
Updated the minimum for the Free Weight Area	Pg. 15
Updated Ceilings and Soffits Section	Pg. 17
Removed the color Grey as an option for wall protection	Pg. 46, 107 & 108
Removed the Platinum cultured stone as an option for the Gallery Scheme. Replaced with the Mohave cultured stone	Pg. 47
Updated General Club Lighting in Interior Fixtures & Accessories	Pg. 51
Updated Furniture in Interior Fixtures & Accessories	Pg. 53
Updated General HVAC in Building Systems	Pg. 60
Updated the paint transition detail	Pg. 99
Added section "Non-traditional Leased Spaces"	Pg. 19-22
	September 2017
Description	Section
Update Sherwin Williams Ceiling Dryfall Paint spec	Pg. 36 & 43
Correct T-3 Tile size	Pg. 38 & 45
Updated minimum sq. ft. size requirements for Functional Training area.	Pg. 11

